



PAVEMENT MARKING SCHEDULE

STATION LOCATION	70300100 SHORT-TERM PAVEMENT MARKING FOOT	70300200 TEMPORARY PAVEMENT MARKING FOOT	70301000 WORK ZONE PAVEMENT MARKING REMOVAL SQ FT	78001110 PAINT PAVEMENT MARKING-LINE 4" FOOT	78100100 RAISED REFLECTIVE PAVEMENT MARKER EACH	78300100 PAVEMENT MARKING REMOVAL SQ FT
MULE CREEK						
MILLED PAVEMENT APPLICATION	110.0					
PRIME COAT APPLICATION (2 APPLICATIONS)	220.0					
BINDER COURSE APPLICATION (2 LIFTS)	220.0					
LIFT SURFACE COURSE APPLICATION	110.0		36.7			
394+00.00 TO 405+00.00, LT EDGE		1100.0		1100.0		
394+00.00 TO 405+00.00, RT EDGE		1100.0		1100.0		
394+00.00 TO 398+00.00, C.L. SKIP-DASH		100.0		100.0		
398+00.00 TO 405+00.00, C.L. SOLID-DASH		875.0		875.0		
394+00.00 TO 405+00.00					14	
395+70.00 TO 404+52.00, RT (SOLID) STAGE I						294.0
394+14.00 TO 395+91.46, C.L. (SKIP-DASH) STAGE I						14.7
403+63.46 TO 405+75.50, C.L. (SKIP-DASH) STAGE I						17.7
395+80.00 TO 396+99.25, LT (SOLID) STAGE II						40.0
402+75.00 TO 403+75.00, LT (SOLID) STAGE II						33.3
BIG MUDDY CREEK						
MILLED PAVEMENT APPLICATION	95.0					
PRIME COAT APPLICATION (2 APPLICATIONS)	190.0					
BINDER COURSE APPLICATION (2 LIFTS)	190.0					
LIFT SURFACE COURSE APPLICATION	95.0		31.7			
569+00.00 TO 578+50.00, LT EDGE		950.0		950.0		
569+00.00 TO 578+50.00, RT EDGE		950.0		950.0		
569+00.00 TO 576+00.00, C.L. SOLID-DASH		875.0		875.0		
576+00.00 TO 578+50.00, C.L. SKIP-DASH		62.5		62.5		
569+00.00 TO 578+50.00					12	
569+60.00 TO 577+40.00, RT (SOLID) STAGE I						260.0
568+07.00 TO 569+68.40, C.L. (SKIP-DASH) STAGE I						13.3
577+51.38 TO 579+15.00, C.L. (SKIP-DASH) STAGE I						13.7
569+90.00 TO 571+00.00, LT (SOLID) STAGE II						36.7
576+22.00 TO 577+25.00, LT (SOLID) STAGE II						34.3
TOTALS	1230.0	6012.5	68.3	6012.5	26	757.7

EARTHWORK SCHEDULE

STATION LOCATION	20200100 EARTH EXCAVATION CU YD	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%) CU YD	EMBANKMENT CU YD	20400800 FURNISHED EXCAVATION WASTE (+) OR SHORTAGE (-) CU YD
MULE CREEK				
394+00.00 TO 398+98.86	48.5	36.4	361.6	-325.2
399+74.03 TO 405+00.00	87.4	65.6	3573.4	-3507.9
BIG MUDDY CREEK				
569+00.00 TO 574+20.04	621.1	465.8	617.2	-151.3
575+47.77 TO 578+50.00	53.8	40.3	65.7	-25.3
CULVERT EXTENSION-DITCH	37.2	27.9	0.0	27.9
TOTALS	848.0	636.0	4617.9	-3981.9

TEMPORARY ACCESS

STATION LOCATION	X4021000 TEMPORARY ACCESS (PRIVATE ENTRANCE) EACH
MULE CREEK	
403+59.71, RT	1
404+50.00, LT	1
TOTALS	2

STAGE CONSTRUCTION SCHEDULE

STATION LOCATION	70106500 TEMPORARY BRIDGE TRAFFIC SIGNALS EACH	70106700 TEMPORARY RUMBLE STRIPS EACH	70400100 TEMPORARY CONCRETE BARRIER FOOT	70400200 RELOCATE TEMPORARY CONCRETE BARRIER FOOT	70030250 IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3 EACH	70030350 IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3 EACH
MULE CREEK						
STAGE CONSTRUCTION (I & II)	1	6				
STAGE I CONSTRUCTION			850.0			
STAGE II CONSTRUCTION				750.0		
395+78.10, 4.9' LT (STAGE I)					1	
403+77.41, 4.7' LT (STAGE I)					1	
396+03.00, 4.2' RT (STAGE II)						1
403+52.50, 4.3' RT (STAGE II)						1
BIG MUDDY CREEK						
STAGE CONSTRUCTION (I & II)	1	6				
STAGE I CONSTRUCTION			687.5			
STAGE II CONSTRUCTION				675.0		
569+72.00, 4.9' LT (STAGE I)					1	
572+84.00, 3.5' RT (STAGE I)					1	
573+71.50, 3.5' RT (STAGE I)					1	
577+46.15, 4.7' LT (STAGE I)					1	
570+21.75, 4.1' RT (STAGE II)						1
577+96.23, 4.3' RT (STAGE II)						1
TOTALS	2	12	1537.5	1425.0	6	4

FILE NAME = #FILEL#	USER NAME = #USER#	DESIGNED - JDS 02/07/08	REVISED -
		DRAWN - JDS 09/24/08	REVISED -
		CHECKED - RJA 09/17/08	REVISED -
		DATE - 09/26/08	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.
--------	-----------	----	--------	------	---------

F.A.P. RTE. 773	SECTION (108BR-3, 109BIB-1)	COUNTY CUMBERLAND	TOTAL SHEETS 96	SHEET NO. 17
CONTRACT NO. 74237				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				