

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	STATE	FED
				20%	80%
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	14	14	14
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2511	2511	2511
40600300	AGGREGATE (PRIME COAT)	TON	50	50	50
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	1036	1036	1036
40600990	TEMPORARY RAMP	SQ YD	123	123	123
40600995	TEMPORARY RAMP, SPECIAL	SQ YD	614	614	614
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	2072	2072	2072
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	54	54	54
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	443	443	443
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	25966	25966	25966
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	130	130	130
44200152	PAVEMENT PATCHING, TYPE I, 13 INCH	SQ YD	121	121	121
44200156	PAVEMENT PATCHING, TYPE II, 13 INCH	SQ YD	314	314	314
44200160	PAVEMENT PATCHING, TYPE III, 13 INCH	SQ YD	75	75	75
44200162	PAVEMENT PATCHING, TYPE IV, 13 INCH	SQ YD	60	60	60
48203100	HOT-MIX ASPHALT SHOULDERS	TON	56	56	56
60260500	INLETS TO BE ADJUSTED WITH NEW TYPE 3 FRAME AND GRATE	EACH	13	13	13
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	1	1	1
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	12	12	12
67100100	MOBILIZATION	L SUM	1	1	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	1

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	STATE	FED
				20%	80%
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	1
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	352	352	352
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	19894	19894	19894
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2790	2790	2790
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	272	272	272
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	292	292	292
* 70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	11349	11349	11349
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	352	352	352
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	19894	19894	19894
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2790	2790	2790
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	272	272	272
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	292	292	292
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	267	267	267
* 88500100	INDUCTIVE LOOP DETECTOR	EACH	18	18	18
* 88600100	DETECTOR LOOP, TYPE I	FOOT	1058	1058	1058
X0325702	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1	1
X7030300	WET REFLECTIVE TEMPORARY PAVEMENT MARKING TAPE, TYPE III	FOOT	6343	6343	6343
Z0025500	FURNISHING AND INSTALLING PROPERTY MARKERS	EACH	1	1	1
Z0070100	SURVEY MONUMENT COVER ASSEMBLY	EACH	1	1	1

* SPECIALTY ITEMS