

**GENERAL NOTES**

THIS SECTION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE PLANS; THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION" ADOPTED January 1, 2007; THE SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS INDICATED ON THE CHECK SHEET, AND "THE SPECIAL PROVISIONS" INCLUDED IN THIS PROPOSAL.

THE PROPOSED PROJECT IS LOCATED ON IL 185 IN FAYETTE COUNTY. THE PROJECT BEGINS ON THE EAST EDGE OF COUNTY ROAD 350 E. AT SHAFTER AND EXTENDS 5.04 MILES SOUTH TO THE NORTH EDGE OF US 40 IN VANDALIA. THE WORK INCLUDED IN SECTION D7 HMA SAFETY SHLD 2009 CONSIST OF HOT-MIX ASPHALT SHOULDERS WITH RUMBLE STRIPS AND AGGREGATE SHOULDERS.

THE CONTRACTOR SHALL PROVIDE INTERNET ACCESS TO THE HOT-MIX ASPHALT PLANT QUALITY CONTROL LAB SO THAT HOT-MIX ASPHALT PLANT REPORTS CAN BE E-MAILED TO THE DISTRICT HEADQUARTERS. THIS WORK SHALL BE INCLUDED IN THE COST OF HOT-MIX ASPHALT ITEMS.

AGGREGATE SHOULDERS, TYPE B SHALL BE CRUSHED STONE, CRUSHED CONCRETE, OR RAP.

THE MATERIAL EXCAVATED FOR THE CONSTRUCTION OF THE HMA SHOULDERS SHALL BE REMOVED FROM THE PROJECT ACCORDING TO ARTICLE 202.03 OF THE STANDARD SPECIFICATIONS. THE REMOVAL OF THE EXCAVATED MATERIAL SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE PER UNIT FOR EXCAVATING AND GRADING EXISTING SHOULDER.

THE TOTAL QUANTITY OF PAINT PAVEMENT MARKING - LINE 4" CONSISTS OF 52713 FEET OF WHITE AND 6652 FEET OF YELLOW.

THE FOLLOWING MIXTURE REQUIREMENTS ARE APPLICABLE FOR THIS PROJECT:

HMA SHOULDER

MIXTURE USE: HMA SHOULDERS, 8"  
 APPLICATION: HOT-MIX ASPHALT SHOULDERS  
 PG GRADE: PG 58-22  
 DESIGN AIR VOIDS: 4.0% @ NDESIGN = 30  
 MIXTURE COMPOSITION: IL-19.0L  
 FRICTION AGGREGATE: N/A

**INDEX OF SHEETS**

SHEET NO.	ITEM
1	COVER SHEET
2	INDEX OF SHEETS
2	GENERAL NOTES
3	SUMMARY OF QUANTITIES
4-5	TYPICAL CROSS-SECTIONS
6	SCHEDULES
7	RUMBLE STRIP & HMA SHOULDER DETAIL

THE FOLLOWING STANDARDS ARE A PART OF THESE PLANS AND ARE INCLUDED AFTER SHEET NO. 7:

STD. NO.	DESCRIPTION
000001-05	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001006	DECIMAL OF AN INCH AND OF A FOOT
482001-02	HMA SHOULDER ADJACENT TO FLEXIBLE PAVEMENT
701011-02	OFF-RD MOVING OPERATIONS, 2L, 2W, DAY ONLY
701326-03	LANE CLOSURE, 2L, 2W, PAVEMENT WIDENING, FOR SPEEDS ? 45 MPH
701901-01	TRAFFIC CONTROL DEVICES

FILE NAME =	USER NAME = steffennk	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>GENERAL NOTES &amp; INDEX OF SHEETS</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
es:\pwork\PWIDOT\STEFFENMK\0123251\074383-shr-cover.dgn	DRAWN -	REVISED -	777			.	Fayette	7	2	
PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -	CONTRACT NO. 74383							
PLOT DATE = 3/19/2009	DATE -	REVISED -	SCALE:			SHEET NO. OF 7 SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT		