

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	60-15VB-1&2	MADISON	149	4
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO. 76634				

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN						
				1000	SEC 60-15VB-1 X171-5B	SEC 60-15VB-2 X171-5B	80% FEDERAL 20% STATE			
M5030390	BRIDGE DECK GROOVING	SQ M	2421		1181	1240				
M5030450	PROTECTIVE COAT	SQ M	2741		1339	1402				
M5050105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		0.5	0.5				
M5080205	REINFORCEMENT BARS, EPOXY COATED	KG	195870		86570	109300				
M5110100	SLOPE WALL 100 MM	SQ M	2235		1081	1154				
M5120176	FURNISHING METAL SHELL PILES 356MM X 6.35MM	METER	4126.0		1801.0	2325.0				
M5120335	DRIVING PILES	METER	4126.0		1801.0	2325.0				
M5120900	TEMPORARY SHEET PILING	SQ M	1496		767	729				
M5200225	PREFORMED JOINT STRIP SEAL	METER	90.6		46.0	44.6				
M5210022	ANCHOR BOLTS, M24	EACH	76		36	40				
M5210024	ANCHOR BOLTS, M36	EACH	80		36	44				
M542E148	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 1050MM	EACH	2	2						
M542E152	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 1200MM	EACH	2	2						
M542E168	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 1800MM	EACH	2	2						
M542T215	PIPE CULVERTS, CLASS C, TYPE 1 300MM (TEMPORARY)	METER	51.5	51.5						
M5429760	PIPE CULVERTS, TYPE 7 RCCP 1500MM	METER	113.0	113.0						
M5870300	CONCRETE SEALER	SQ M	292		149	143				
M5910100	GEOCOMPOSITE WALL DRAIN	SQ M	193		98	95				
M5930100	CONTROLLED LOW-STRENGTH MATERIAL	CU M	7	7						
M6011100	PIPE UNDERDRAINS FOR STRUCTURES 100MM	METER	144.9		71.1	73.8				
MX033777	PIPE CULVERTS, TYPE 5 RCCP 1050MM (JACKED)	METER	28.5	28.5						
MX033778	PIPE CULVERTS, TYPE 5 RCCP 1200MM (JACKED)	METER	29.0	29.0						
20076600	TRAINERS	HOUR	3000	3000						
M542E248	STEEL END SECTIONS 1050 MM	EACH	2	2						
M542E252	STEEL END SECTIONS 1200 MM	EACH	2	2						
MX030575	STEEL CASING PIPE BORED AND JACKED 1050 MM	METER	30.5	30.5						
MX030576	STEEL CASING PIPE BORED AND JACKED 1200 MM	METER	30.5	30.5						

© 1980

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SUMMARY OF QUANTITIES FAP 310 (IL 255) SECTION 60-15VB-1 & 2 MADISON COUNTY DRAWN BY EBB CHECKED BY
NAME	DATE	

Rev. 5-18-09

DATE

CHECKED BY

ebb

p:\00f1es\000024\Railroad-Bridge\ROADPLANS\SumQuant\015f.dgn