

ebb

p:\00files\000024\Railroad-Bridge\ROADPLANS\SumQuant\015f.dgn

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	60-15VB-1&2	MADISON	149	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 76634				

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					
				URBAN					
				80% FEDERAL 20% STATE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000	SEC 60-15VB-1 X171-58	SEC 60-15VB-2 X171-58			
28000300	TEMPORARY DITCH CHECKS	EACH	22	22					
28000500	INLET AND PIPE PROTECTION	EACH	7	7					
50500505	STUD SHEAR CONNECTORS	EACH	12354		6183	6171			
50800515	BAR SPLICERS	EACH	296		150	146			
51203200	TEST PILE METAL SHELLS	EACH	4		2	2			
51500100	NAME PLATES	EACH	2		1	1			
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	49		27	22			
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	9			9			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	30	30					
67100100	MOBILIZATION	L SUM	1	1					
Z0041500	PLUG EXISTING CULVERTS	EACH	1	1					
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1					
Z0065100	SETTLEMENT PLATFORMS	EACH	4	4					
M2010500	TREE REMOVAL, HECTARES	HA	2.0	2.0					
M2020010	EARTH EXCAVATION	CU M	6825	6825					
M2040800	FURNISHED EXCAVATION	CU M	140,080	140,080					
M2070400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU M	353		181	172			
M2500200	SEEDING, CLASS 2	HA	4.2	4.2					
M2500400	NITROGEN FERTILIZER NUTRIENT	KG	420	420					
M2500500	PHOSPHORUS FERTILIZER NUTRIENT	KG	420	420					
M2500600	POTASSIUM FERTILIZER NUTRIENT	KG	420	420					
M2510115	MULCH, METHOD 2	HA	2.9	2.9					
M2510630	EROSION CONTROL BLANKET	SQ M	13101	13101					
M2800250	TEMPORARY EROSION CONTROL SEEDING	KG	1848	1848					
M2800400	PERIMETER EROSION BARRIER	METER	245	245					
M2800407	PERIMETER EROSION BARRIER, MODIFIED	METER	325	325					
M2810105	STONE RIPRAP, CLASS A3	SQ M	169		92	77			
M2810725	STONE DUMPED RIPRAP, CLASS B3	SQ M	282	282					
M2811840	RIPRAP FOR STILLING BASIN	M TON	204	204					
M2820200	FILTER FABRIC	SQ M	271	102	92	77			
M4021010	AGGREGATE SURFACE COURSE, TYPE B	M TON	2659	2659					
M5020100	STRUCTURE EXCAVATION	CU M	2203		1039	1164			
M5030280	CONCRETE ENCASEMENT	CU M	26.9		13.6	13.3			
M5030290	FORM LINER TEXTURED SURFACE	SQ M	168		86	82			
M5030350	CONCRETE STRUCTURES	CU M	1240.5		626.8	613.7			
M5030360	CONCRETE SUPERSTRUCTURE	CU M	631.5		307.2	324.3			

Rev. 6-3-09
Rev. 5-28-09

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
FAP 310 (IL 255)
SECTION 60-15VB-1 & 2
MADISON COUNTY
DRAWN BY EBB
CHECKED BY
DATE