CONTRACT NO. 76709

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	60-10K-1, 60-10HB	MADISON	420	5
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000-1A						X771-2A	I000-1A			
				I-70 & FRONTAGE RD	IL 162	I-70 & FRONTAGE RD	IL 162	IL 162 @ RAMPS & EAST FRONT. RD	IL 162 @ WEST FRONT. RD				I-55/70	IL 162
				ROADWAY 100% FED	ROADWAY 100% FED	ROADWAY 100% FED	ROADWAY 100% FED	TRAFFIC SIGNALS 100% FED	TRAFFIC SIGNALS 100% FED	BRIDGE REPLACEMENT 100% FED	MSE WALLS 100% FED	SIGNING 100% FED	HIGHWAY LIGHTING 100% FED	HIGHWAY LIGHTING 100% FED
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	3625	1812.5	1812.5									
28000300	TEMPORARY DITCH CHECKS	EACH	114	30	23	58	3							
28000400	PERIMETER EROSION BARRIER	FOOT	4258	2765	1292	201								
28000500	INLET AND PIPE PROTECTION	EACH	93	41	2	30	20							
28100127	STONE RIPRAP, CLASS B4	SQ YD	400	17		383								
28200200	FILTER FABRIC	SQ YD	400	17		383								
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	111109	35162	6531	44197	25219							
30201500	LIME	TON	1974	674	125	692	483							
31200100	STABILIZED SUB-BASE 4"	SQ YD	50289			26030	24259							
35100100	AGGREGATE BASE COURSE, TYPE A	TON	957	330	99	490	38							
35101100	AGGREGATE BASE COURSE, TYPE A 12"	SQ YD	2482			96	2386							
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	193	77			116							
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	1342	981			361							
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	7000	7000										
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	17.6	11.8	5.8									
40600300	AGGREGATE (PRIME COAT)	TON	140.4	92.4	48									
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	128	128										
40600895	CONSTRUCTING TEST STRIP	EACH	5	3	2									
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	174		174									
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	1117		1117									
40603570	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N90	TON	916			916								
40701871	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9 1/2"	SQ YD	9572	9572										
40701891	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 10 1/2"	SQ YD	2042	2042										
40701906	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 11 1/4"	SQ YD	3947	3947										
40701916	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 11 3/4"	SQ YD	6186	6186										
40701951	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 13 1/2"	SQ YD	7918	7918										
40701961	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 14"	SQ YD	2510	2510										
40701976	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 14 3/4"	SQ YD	5119	5119										
40701991	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 15 1/2"	SQ YD	4327	4327										

PLOT DATE = 2/18/2009
FILE NAME = c:\pwidot\KEFLARCL\dms88415\pln88903a.dgn
PLOT SCALE = 50.000 ' / IN.
REFERENCE = REF