

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	60-10K-1, 60-10HB	MADISON	420	12
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

I000-1A

X771-2A

I000-1A

ILLINOIS DEPARTMENT OF TRANSPORTATION			TOTAL QUANTITIES	I-70 & FRONTAGE RD		I-70 & FRONTAGE RD		IL 162 e RAMP & EAST FRONT. RD		IL 162 e WEST FRONT. RD		I-55/70		IL 162	
CODE NO	ITEM	UNIT		ROADWAY 100% FED	ROADWAY 100% FED	ROADWAY 100% FED	ROADWAY 100% FED	TRAFFIC SIGNALS 100% FED	TRAFFIC SIGNALS 100% FED	BRIDGE REPLACEMENT 100% FED	MSE WALLS 100% FED	SIGNING 100% FED	HIGHWAY LIGHTING 100% FED	HIGHWAY LIGHTING 100% FED	
81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	5				4	1							
81603010	UNIT DUCT, 600V, 2-1C NO.10, 1/C NO.10 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT	95									95			
81603025	UNIT DUCT, 600V, 2-1C NO.4, 1/C NO.4 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	18419									18419			
81603035	UNIT DUCT, 600V, 2-1C NO.6, 1/C NO.6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	5220										5220		
81701125	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE USE) 1/C NO. 1/0	FOOT	691									306	385		
81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	1447									1447			
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	24426				2910	737				16246	4533		
82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	116									87	29		
82105700	LUMINAIRE, SODIUM VAPOR, HIGH MAST, HORIZONTAL MOUNT, 750 WATT	EACH	16									16			
82107300	UNDERPASS LUMINAIRE, 150 WATT, HIGH PRESSURE SODIUM VAPOR	EACH	10									10			
82109200	SIGN LIGHTING LUMINAIRE, 150 WATT, HIGH PRESSURE SODIUM	EACH	5									5			
82500510	LIGHTING CONTROLLER TYPE CB-RCS 60AMP - 240 VOLT	EACH	2										2		
82500540	LIGHTING CONTROLLER TYPE CB-RCS 100AMP - 480VOLT	EACH	2									2			
83024500	LIGHT POLE, ALUMINUM, TRANSFORMER BASE, 50 FT. M. H., 12 FT. MAST ARM	EACH	116									87	29		
83503200	LIGHT TOWER, 110 FT. MOUNTING HEIGHT, LUMINAIRE MT. - 3	EACH	2									2			
83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	612									609	203		
83700100	LIGHT TOWER FOUNDATION	FOOT	72									72			
84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	15									15			
84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	1										1		
84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	1										1		
85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	2				1	1							
85700300	FULL-ACTUATED CONTROLLER AND TYPE V CABINET	EACH	1				1								
86000100	MASTER CONTROLLER	EACH	1				1								
84200802	POLE FOUNDATION REMOVE	EACH	15									15			
84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1										1		

*Specialty Items

Rev.

PLOT DATE = 2/16/2009
 PLOT SCALE = 5/8" = 1'-0"
 REFERENCE = SHEET