

HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9 1/2"

LOCATION	AREA -STAGE I (SQ. YD.)	AREA -STAGE II (SQ. YD.)	AREA -STAGE III (SQ. YD.)
SOUTHWEST FRONTAGE ROAD			
STA. 50+57.75 TO 59+59.32	2,817		
STA. 52+18.92 TO 53+96.89		129	
STA. 55+84.33 TO 58+85.83		121	
SOUTHEAST FRONTAGE ROAD			
STA. 11+72.61 TO 18+94.27	988		
STA. 26+90.31 TO 35+20.05	1,928		
STA. 11+82.78 TO 17+19.42		746	
STA. 32+42.69 TO 33+66.00		11	
STA. 31+60.52 TO 34+03.32			162

HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9 1/2"			
	5,733	1,007	162
	SQ. YD.	SQ. YD.	SQ. YD.
TOTAL=	6,902		
	SQ. YD.		

HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 10 1/2"

LOCATION	AREA -STAGE I (SQ. YD.)	AREA -STAGE II (SQ. YD.)	AREA -STAGE III (SQ. YD.)
NORTHWEST FRONTAGE ROAD			
STA. 19+84.12 TO 21+94.10	428		
STA. 22+72.12 TO 23+96.49	124		
STA. 23+91.87 TO 27+68.78	467		
STA. 24+38.88 TO 28+89.39		497	
STA. 24+41.03 TO 28+89.37			493
STA. 25+98.89 TO 27+97.53			33

HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 10 1/2"			
	1,019	497	526
	SQ. YD.	SQ. YD.	SQ. YD.
TOTAL=	2,042		
	SQ. YD.		

HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 11 1/4"

LOCATION	AREA -STAGE I (SQ. YD.)	AREA -STAGE II (SQ. YD.)	AREA -STAGE III (SQ. YD.)
NORTHEAST FRONTAGE ROAD			
STA. 35+34.12 TO 40+00.00	1,259		
STA. 40+00.00 TO 54+71.53	2,688		

HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 11 1/4", TOTAL=			
	3,947	0	0
	SQ. YD.	SQ. YD.	SQ. YD.
TOTAL=	3,947		
	SQ. YD.		

HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 13 1/2"

LOCATION	AREA -STAGE I (SQ. YD.)	AREA -STAGE II (SQ. YD.)	AREA -STAGE III (SQ. YD.)
RAMP A			
STA. 51+34.54 TO 53+55.45	199		
STA. 60+35.00 TO 64+27.21		674	
STA. 50+00.00 TO 58+99.09		1,158	
STA. 50+00.00 TO 58+99.09			1,169
RAMP B			
STA. 99+85.34 TO 111+04.60		1,059	
RAMP C			
STA. 18+39.20 TO 19+68.33	128		
STA. 150+00.00 TO 160+19.61			1,361
RAMP D			
STA. 19+14.26 TO 20+00.00	16		
STA. 200+85.07 TO 203+13.72	97		
STA. 200+48.46 TO 204+53.24		885	
STA. 205+43.80 TO 214+41.53			1,172

HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 13 1/2", TOTAL=			
	440	3,776	3,702
	SQ. YD.	SQ. YD.	SQ. YD.
TOTAL=	7,918		
	SQ. YD.		

HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 14 3/4"

LOCATION	AREA -STAGE I (SQ. YD.)	AREA -STAGE II (SQ. YD.)	AREA -STAGE III (SQ. YD.)
IL 162 WEST OF I-70			
STA. 474+79.38 TO 490+00.00	2,815		
STA. 490+00.00 TO 492+31.71	231		
STA. 491+96.62 TO 494+88.00	337		
STA. 494+09.50 TO 498+45.49	364		
STA. 494+56.99 TO 497+48.10	168		
STA. 475+26.64 TO 485+49.37		974	
IL 162 EAST OF I-70			
STA. 505+07.36 TO 506+93.71	216		
STA. 508+17.00 TO 509+00.00	12		
STA. 509+00.00 TO 509+12.41	2		

HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 14 3/4", TOTAL=			
	4,145	974	0
	SQ. YD.	SQ. YD.	SQ. YD.
TOTAL=	5,119		
	SQ. YD.		

PROCESSING MODIFIED SOIL, 12"

LOCATION	AREA -STAGE I (SQ. YD.)	AREA -STAGE II (SQ. YD.)	AREA -STAGE III (SQ. YD.)	TOTAL ARE (SQ. YD.)	VOLUME CU. YD.	QTY* TON
SOUTHWEST FRONTAGE ROAD						
STA. 50+57. TO 59+59.32	2,996			2,996	999	57.4
STA. 52+18.9 TO 53+96.89		170		170	57	3.3
STA. 55+84. TO 58+85.83		152		152	51	2.9
	2,996	322	0	3,318		

LOCATION	AREA -STAGE I (SQ. YD.)	AREA -STAGE II (SQ. YD.)	AREA -STAGE III (SQ. YD.)	TOTAL ARE (SQ. YD.)	VOLUME CU. YD.	QTY* TON
SOUTHEAST FRONTAGE ROAD						
STA. 11+72.6 TO 18+94.27	1,077			1,077	359	20.6
STA. 26+90.3 TO 35+20.05	2,083			2,083	694	39.9
STA. 11+82.8 TO 17+19.40		849		849	283	16.3
STA. 32+42. TO 33+66.00		25		25	8	0.5
STA. 31+60.5 TO 34+03.32			222	222	74	4.3
	3,160	874	222	4,256		

LOCATION	AREA -STAGE I (SQ. YD.)	AREA -STAGE II (SQ. YD.)	AREA -STAGE III (SQ. YD.)	TOTAL ARE (SQ. YD.)	VOLUME CU. YD.	QTY* TON
NORTHWEST FRONTAGE ROAD						
STA. 19+84.1 TO 21+94.10	451			451	150	8.6
STA. 22+72.1 TO 23+96.12	146			146	49	2.8
STA. 23+91.8 TO 27+68.60	509			509	170	9.8
STA. 24+40. TO 28+89.37		584		584	195	11.2
STA. 24+41.0 TO 28+89.37			543	543	181	10.4
STA. 25+98. TO 27+97.53			74	74	25	1.4
	1,106	584	617	2,307		

LOCATION	AREA -STAGE I (SQ. YD.)	AREA -STAGE II (SQ. YD.)	AREA -STAGE III (SQ. YD.)	TOTAL ARE (SQ. YD.)	VOLUME CU. YD.	QTY* TON
NORTHEAST FRONTAGE ROAD						
STA. 35+34.1 TO 40+00.00	1,355			1,355	452	26.0
STA. 40+00. TO 54+71.53	2,858			2,858	953	54.8
	4,213	0	0	4,213		

LOCATION	AREA -STAGE I (SQ. YD.)	AREA -STAGE II (SQ. YD.)	AREA -STAGE III (SQ. YD.)	TOTAL ARE (SQ. YD.)	VOLUME CU. YD.	QTY* TON
TEMPORARY RAMP A						
STA. 60+35. TO 64+27.21		764		764	255	14.6
STA. 50+00. TO 58+99.09		1,329		1,329	443	25.5
STA. 50+00. TO 58+99.09			1,352	1,352	451	25.9
TEMPORARY RAMP B						
STA. 99+85. TO 111+04.60		1,278		1,278	426	24.5
TEMPORARY RAMP C						
STA. 150+00 TO 160+19.61			1,539	1,539	513	29.5
TEMPORARY RAMP D						
STA. 200+48. TO 204+53.24	109	969		1,078	323	18.6
STA. 205+43. TO 214+41.53			1,528	1,528	509	29.3
	109	4,340	4,419	8,868		

LOCATION	AREA -STAGE I (SQ. YD.)	AREA -STAGE II (SQ. YD.)	AREA -STAGE III (SQ. YD.)	TOTAL ARE (SQ. YD.)	VOLUME CU. YD.	QTY* TON
IL 162 WEST OF I-70						
STA. 474+79. TO 490+00.00	2,984			2,984	995	57.2
STA. 490+00 TO 492+31.71	257			257	86	4.9
STA. 494+09. TO 498+45.49	413			413	138	7.9
STA. 475+26. TO 485+49.37		1,088		1,088	363	20.9
	3,654	1,088	0	4,742		

PROCESSING MODIFIED SOIL, TOTAL=		27,704	528.9
	SQ. YD.		TON

**AGGREGATE (PRIME COAT)
BITUMINOUS MATERIALS (PRIME COAT)**

TYPE	AGGREGATE BITUMINOUS			
	SQ YD	POUNDS	TON	TON
HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9 1/2"	6,902	34,510	17.3	2.2
HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 10 1/2"	2,042	10,210	5.1	0.6
HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 11 1/4"	3,947	19,735	9.9	1.2
HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 13 1/2"	7,718	38,590	19.3	2.4
HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 14 3/4"	5,119	25,595	12.8	1.6
TOTAL=		64.3	8.1	
		TON	TON	

TYPE	RATE	
	AREA (SQ YD) x 5 (LB/SQ YD)	AREA (SQ YD) x .0003129 (Tons/SQ YD)
AGGREGATE (PRIME COAT)		
BITUMINOUS MATERIALS (PRIME COAT)		

GEOTEXTILE RETAINING WALL

LOCATION	AVERAGE HEIGHT (FT.)	AREA (SQ. FT.)
IL 162 WEST OF I-70		
STA. 493+50 TO 494+00	1.00	50
STA. 494+00 TO 494+50	2.07	104
STA. 494+50 TO 495+00	2.39	120
STA. 495+00 TO 495+50	2.69	135
STA. 495+50 TO 496+00	3.04	152
STA. 496+00 TO 496+50	3.80	190
STA. 496+50 TO 497+00	4.42	221
STA. 497+00 TO 497+50	4.84	242
STA. 497+50 TO 498+00	5.07	254
STA. 498+00 TO 498+50	4.98	249
STA. 498+50 TO 498+70	4.53	159
IL 162 EAST OF I-70		
STA. 500+30 TO 500+50	4.34	152
STA. 500+50 TO 501+00	4.09	205
STA. 501+00 TO 501+50	3.65	183
STA. 501+50 TO 502+00	2.99	150
STA. 502+00 TO 502+50	1.99	100
STA. 503+00 TO 503+50	1.33	67
STA. 503+00 TO 504+00	0.73	18

GEOTEXTILE RETAINING WALL, TOTAL=		2,750
	SQ. FT.	

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULE OF QUANTITIES
MAINTENANCE OF TRAFFIC - 1**

REVISIONS	
NAME	DATE

DRAWN BY: RDT

PLOT DATE: *DATE-TIME*

DATE _____ BY _____
 PLAN NO. _____
 SURVEYED _____
 ALIGNED _____
 CHECKED _____
 BY _____
 DATE _____