

PAVEMENT REMOVAL

LOCATION	AREA -STAGE I (SQ. YD.)	AREA -STAGE II (SQ. YD.)	AREA -STAGE III (SQ. YD.)
SOUTHWEST FRONTAGE ROAD			
STA. 50+57.75 TO 59+59.32	2,817		
STA. 52+18.92 TO 53+96.89		129	
STA. 55+84.33 TO 58+85.83		121	
SOUTHEAST FRONTAGE ROAD			
STA. 11+72.61 TO 18+94.27	988		
STA. 26+90.31 TO 35+20.05	1,928		
STA. 11+82.78 TO 17+19.42		746	
STA. 32+42.69 TO 33+66.00		11	
STA. 31+60.52 TO 34+03.32			162
NORTHWEST FRONTAGE ROAD			
STA. 19+84.12 TO 21+94.10	428		
STA. 22+72.12 TO 23+96.49	124		
STA. 23+91.87 TO 27+68.78	467		
STA. 24+38.88 TO 28+89.39		497	
STA. 24+41.03 TO 28+89.37			493
STA. 25+98.89 TO 27+97.53			33
NORTHEAST FRONTAGE ROAD			
STA. 35+34.12 TO 40+00.00	1,259		
STA. 40+00.00 TO 54+71.53	2,688		
RAMP A			
STA. 51+34.54 TO 53+55.45	199		
STA. 60+35.00 TO 64+27.21		674	
STA. 50+00.00 TO 58+99.09		1,158	
STA. 50+00.00 TO 58+99.09			1,169
RAMP B			
STA. 99+85.34 TO 111+04.60		1,059	
RAMP C			
STA. 18+39.20 TO 19+68.33	128		
STA. 150+00.0 TO 160+19.61			1,361
RAMP D			
STA. 19+14.26 TO 20+00.00	16		
STA. 200+85.0 TO 203+13.72	97		
STA. 200+48.4 TO 204+53.24		885	
STA. 205+43.8 TO 214+41.53			1,172
IL 162 WEST OF I-70			
STA. 474+79.38 TO 490+00.00	2,815		
STA. 490+00.0 TO 492+31.71	231		
STA. 491+96.62 TO 494+88.00	337		
STA. 494+09.5 TO 498+45.49	364		
STA. 494+56.99 TO 497+48.10	168		
STA. 475+26.64 TO 485+49.37		974	
IL 162 EAST OF I-70			
STA. 505+07.3 TO 506+93.71	216		
STA. 508+17.00 TO 509+00.00	12		
STA. 509+00.0 TO 509+12.41	2		

PAVEMENT REMOVAL, TOTAL = 15,284 SQ. YD. 6,254 SQ. YD. 4,390 SQ. YD.  
 25,928 SQ. YD.

TEMPORARY DRAINAGE

LOCATION	PIPE CULVERTS, CLASS D, TYPE 1 TEMPORARY					PIPE CULVERTS, CLASS D, TYPE 2 (TEMPORARY)			TEMPORARY INLET EACH
	12" L.F.	15" L.F.	18" L.F.	24" L.F.	30" L.F.	24" L.F.	36" L.F.	48" L.F.	
STAGE I									
IL ROUTE 162									
STA. 479+60.75		19							
EAST FRONTAGE ROAD									
STA. 33+96.60			90						
STA. 23+85.70			45						
TEMP. EAST FRONTAGE ROAD									
STA. 116+88.00									1
STA. 116+88.00									36
STA. 114+50.00									100
STA. 113+50.00									100
STA. 112+50.00									300
WEST FRONTAGE ROAD									
STA. 23+54.30				50					
STA. 24+79.00				50					
STA. 25+87.50				35					
STAGE 2									
IL ROUTE 162									
STA. 492+98.00							60		
EAST FRONTAGE ROAD									
STA. 14+98.00				14					
WEST FRONTAGE ROAD									
STA. 16+45.80						50		45	
STA. 16+78.00									
STA. 26+09.00				20					
STA. 27+00.00				105					
RAMP A									
STA. 20+91.30							35		
RAMP B									
STA. 104+24.00							40		
STA. 104+75.00		272							
STA. 107+50.00		99							1
TOTAL =	929	19	345	64	40	85	60	45	5

LOCATION	TEMPORARY PAVEMENT MARKING 4 INCH	
	WHITE SOLID LINE FOOT	YELLOW SOLID LINE FOOT
STAGE I		
West Frontage Road (South Leg)		
Sta. 50+30 to Sta. 60+00	970	970
Sta. 50+30 to Sta. 60+00	970	970
West Frontage Road (North Leg)		
Sta. 5+00 to Sta. 8+00	300	300
Sta. 5+00 to Sta. 8+00	300	300
Sta. 2+30 to Sta. 8+50	620	620
Sta. 2+30 to Sta. 8+50	620	620
East Frontage Road (South Leg)		
Sta. 24+50 to Sta. 16+00	850	850
Sta. 24+50 to Sta. 16+00	850	850
Sta. 158+00 to Sta. 150+30	770	770
Sta. 158+00 to Sta. 150+30	770	770
West Frontage Road (North Leg)		
Sta. 100+00 to Sta. 120+50	2,050	2,050
Sta. 100+00 to Sta. 120+50	2,050	2,050
Illinois Route 162		
Sta. 474+00 to Sta. 514+00	4,000	4,000
Sta. 474+00 to Sta. 514+00	4,000	4,000

STAGE II		
West Frontage Road (South Leg)		
Sta. 9+00 to Sta. 19+10	1,010	1,010
Sta. 9+00 to Sta. 19+10	1,010	1,010
West Frontage Road (North Leg)		
Sta. 22+00 to Sta. 29+50	750	750
Sta. 22+00 to Sta. 29+50	750	750
East Frontage Road (South Leg)		
Sta. 11+00 to Sta. 18+00	700	700
Sta. 11+00 to Sta. 18+00	700	700
Sta. 32+00 to Sta. 35+00	300	300
Sta. 32+00 to Sta. 35+00	300	300
East Frontage Road (North Leg)		
Sta. 35+00 to Sta. 37+50	250	250
Sta. 35+00 to Sta. 37+50	250	250
Illinois Route 162		
Sta. 474+00 to Sta. 498+20	2,420	2,420
Sta. 474+00 to Sta. 498+20	2,420	2,420
Ramp A		
Sta. 3+00 to Sta. 17+30	1,430	1,430
Sta. 3+00 to Sta. 17+30	1,430	1,430
Ramp B		
Sta. 3+00 to Sta. 15+00	1,200	1,200
Sta. 3+00 to Sta. 15+00	1,200	1,200
Ramp D		
Sta. 200+25 to Sta. 205+00	475	475
Sta. 200+25 to Sta. 205+00	475	475
STAGE III		
West Frontage Road (North Leg)		
Sta. 23+00 to Sta. 29+50	650	650
Sta. 23+00 to Sta. 29+50	650	650
Illinois Route 162		
Sta. 493+00 to Sta. 518+50	2,550	2,550
Sta. 493+00 to Sta. 518+50	2,550	2,550
Ramp C		
Sta. 149+00 to Sta. 159+50	1,050	1,050
Sta. 149+00 to Sta. 159+50	1,050	1,050
Ramp D		
Sta. 205+00 to Sta. 215+00	1,000	1,000
Sta. 205+00 to Sta. 215+00	1,000	1,000
SUBTOTAL ALL STAGES =	46,690	36,380

TEMPORARY PAVEMENT MARKING LINE - 4" TOTAL = 83,070 FEET

TEMPORARY CONCRETE BARRIER

LOCATION	LENGTH (FOOT)	PRISMATIC BARRIER REFLECTOR (EACH)
IL ROUTE 162 STAGE I		
STA. 497+70.0 TO 501+32.50 LT	362.5	4
STA. 497+70.0 TO 501+32.50 RT	362.5	4
I-70 STAGE I		
STA. 1351+00.0 TO 1359+00.00 NB - LT	800.0	6
STA. 1344+00.0 TO 1356+00.00 SB - LT	1,200.0	7
STA. 1351+00.0 TO 1359+00.00 NB - RT	800.0	6
STA. 1344+00.0 TO 1356+00.00 SB - RT	1,200.0	7
TEMPORARY CONCRETE BARRIER, TOTAL =	4,725	FEET
PRISMATIC BARRIER REFLECTOR, TOTAL =	34	EACH

RELOCATE TEMPORARY CONCRETE BARRIER

LOCATION	LENGTH (FOOT)
IL ROUTE 162 STAGE III	
STA. 497+70.0 TO 501+32.50 LT	362.5
I-70 STAGES II AND III	
STA. 1351+00.0 TO 1359+00.00 NB - LT	800.0
STA. 1351+00.0 TO 1359+00.00 NB - RT	800.0
STA. 1344+00.0 TO 1356+00.00 SB - LT	1,200.0
STA. 1344+00.0 TO 1356+00.00 SB - RT	1,200.0
RELOCATE TEMPORARY CONCRETE BARRIER, TOTAL =	4,362.5 FEET

IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3

LOCATION	EACH
IL ROUTE 162 STAGE I	
STA. 497+70.00 LT	1
STA. 501+32.50 RT	1
I-70 STAGE I	
STA. 1359+00.00 NB	2
STA. 1356+00.00 SB	2
IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3, TOTAL =	6 EACH

RELOCATE IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3

LOCATION	EACH
STA. 497+70.00 LT	1
STA. 501+32.50 RT	1
I-55/70 NORTHBOUND	2
I-55/70 SOUTHBOUND	2
RELOCATE IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3, TOTAL =	6 EACH

CONTRACT NO.: 76709  
 • 60-10K-1, 60-10HB

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES MAINTENANCE OF TRAFFIC - 2

DRAWN BY: ROT

PLOT DATE: \*DATE-TIME\*

REVISIONS	
NAME	DATE

DATE: \_\_\_\_\_ BY: \_\_\_\_\_  
 SURVEYED: \_\_\_\_\_  
 PLAN: \_\_\_\_\_  
 NOTE BOOK: \_\_\_\_\_  
 RT. OF WAY CHECKED: \_\_\_\_\_  
 CADD FILE NAME: \_\_\_\_\_

\*DATE-TIME\*  
 \*JOB-SPEC\*  
 \*REF\*  
 \*DATE-TIME\*