

GENERAL NOTES

- THE STANDARDS AND REVISION NUMBERS SHALL APPLY TO THIS PROJECT.
- THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING MATERIALS.
- ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO UTILITIES WITHIN THE PROJECT AREA BEFORE DIGGING BY CALLING J.U.L.I.E. AND BY NOTIFYING NON-J.U.L.I.E. MEMBERS INDIVIDUALLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:
 - AMERENIP
 - AMERENUE
 - AT&T ILLINOIS
 - VILLAGE OF CASEYVILLE
 - CHARTER COMMUNICATION, INC.
 - MEDIACOM LLC CENTRAL

MEMBERS OF J.U.L.I.E (800) 892-0123 ARE INDICATED BY *. NON-MEMBERS MUST BE NOTIFIED INDIVIDUALLY.

- A QUANTITY OF 1288 FEET OF "TEMPORARY PAVEMENT MARKING - LINE 6" WHITE HAS BEEN INCLUDED IN THE PLANS FOR PAINTING THE BOTTOM 6" OF THE TEMPORARY CONCRETE BARRIER.
- THE CONTRACTOR SHALL FURNISH AND INSTALL WOOD SIGN SUPPORTS IN ACCORDANCE WITH SECTION 730 OF THE STANDARD SPECIFICATIONS, HOWEVER, INSTALLATION BY METHOD "A" (ARTICLE 730.04(A)) SHALL BE THE ONLY METHOD PERMITTED.
- TWO LANE OF TRAFFIC IN EACH DIRECTION SHALL BE MAINTAINED AT ALL TIMES.
- "ROAD CONSTRUCTION AHEAD" SIGNS SHALL BE REQUIRED AT INTERSECTING SIDE ROADS THROUGHOUT THE PROJECT. COST TO BE INCLUDED IN BID PRICES FOR TRAFFIC CONTROL AND PROTECTION.

COMMITMENTS

NONE

RESURFACING SCHEDULE

STATION		RT/LT	BITUMINOUS MATERIAL (PRIME COAT) (TON)	AGGREGATE (PRIME COAT) (TON)	HMA SURF. REMOVAL BUTT-JOINT (SQ YD)	POLYMERIZED HMA SURF. CSE., MIX "E", N105 (TON)	HMA SHOULDERS (TON)
1145+90.00	TO 1146+25.00	RT			217.78		
1145+90.00	TO 1146+63.15	RT					7.96
1145+90.00	TO 1146+90.12	RT	0.13	0.60		39.20	
1145+90.00	TO 1147+17.33	RT					13.82
1150+06.25	TO 1151+33.00	RT					13.82
1150+32.97	TO 1151+33.00	RT	0.13	0.60		39.20	
1150+61.69	TO 1151+33.00	RT					7.96
1150+98.00	TO 1151+33.00	RT			217.78		
TOTAL			0.25	1.20	435.56	78.40	43.56

STAGE CONSTRUCTION SCHEDULE

LOCATION		TEMPORARY CONCRETE BARRIER (FT)	RELOCATE TEMPORARY CONCRETE BARRIER (FT)	IMPACT ATTENUATOR TEMPORARY (EA)	RELOCATE IMPACT ATTENUATOR (EA)
1143+81.50				1	
1143+81.50	TO 1146+55.50	275.00			
1146+55.50	TO 1150+55.50	400.00			
1144+43.50					1
1144+43.50	TO 1146+55.50		212.5		
1146+55.50	TO 1150+55.50		400.00		
1151+62.00					
TOTAL		675.00	612.50	1	1

TEMPORARY PAVEMENT MARKING SCHEDULE

STATION	PAVEMENT MARKING		SHORT-TERM PAVEMENT MARKING (FT)	WORK ZONE PAVEMENT REMOVAL (SQ FT)	RAISED REFLECTIVE PAVEMENT MARKER (EA)	
	LINE 4" (FT)	LINE 6" (FT)				
1121+55.50 TO 1138+55.50	1700.0					
1138+55.50 TO 1156+55.50	EDGE LINES 3600.0		720.0	1440.0	46	
1131+56.50 TO 1156+55.50	CENTERLINE 2499.0		999.6	1166.2		
1143+81.50 TO 1146+55.50	TEMP. BARR.	275.0				
1146+55.50 TO 1150+55.50	TEMP. BARR.	400.00				
1121+55.50 TO 1138+55.50	1700.0					
1138+55.50 TO 1156+55.50	EDGE LINES 3600.0		720.0	1440.0	46	
1131+56.50 TO 1156+55.50	CENTERLINE 2499.0		999.6	1166.2		
1144+43.50 TO 1146+55.50	TEMP. BARR.	212.5				
1146+55.50 TO 1150+55.50	TEMP. BARR.	400.0				
SUB-TOTAL						
TOTAL		15598.0	1287.5	3439.2	5212.4	92

PAVEMENT MARKING SCHEDULE

STATION		4" WHITE LINE (FT)	YELLOW LINE 4" (FT)	RAISED REFLECTIVE PAVEMENT MARKER (EA)
1131+56.00	TO 1156+55.50	SKIP DASH 1249.75		125
1138+55.50	TO 1156+55.50	EDGE LINES 1800.00	1800.00	
SUB-TOTAL		3049.75	1800.00	125
TOTAL		4849.75		125

PAVEMENT MARKING REMOVAL SCHEDULE

STATION		PAVEMENT MARKING REMOVAL (SQ FT)	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL (EA)
1138+55.50	TO 1156+55.50	EDGE LINES 1200.0	
1131+56.50	TO 1156+55.50	SKIP DASH 166.6	125
SUB-TOTAL			
TOTAL		1366.6	125