

PCC PAVEMENT SCHEDULE

STATION TO STATION				LENGTH	WIDTH	PAVEMENT REMOVAL	HES PCC PAVEMENT 10"	SUBBASE GRAN MATL TY A 6"	PROTECTIVE COAT	SIDEWALK REMOVAL	PCC SIDEWALK, SPECIAL	COMB CURB & GUTTER REMOVAL	COMB CONC CURB & GUTTER, TB-6. 24	NOTES
				(FT)	(FT)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ FT)	(SQ FT)	(FT)	(FT)	
FAP 42 - IL 13/127/MAIN ST.														
URBAN LIMITS														
	1262+51.00	TO	1264+93.00	242	29	780	780	780	780					
Rt	1262+76	TO	1264+93						81			227	227	
Lt	1264+65	TO	1265+56			34	34	34	47					Left Radius
Rt	1264+81	TO	1264+93			4	4	4	4			36	36	Right Radius
Lt	1264+60	TO	1265+56						35	223	317			
Rt	1262+76	TO	1262+86			4	4	4	4					Right Radius
FAP 42/841 - IL 13/127/154/WATER ST.														
URBAN LIMITS														
	144' East of 1265+14.6	TO	1266+75.00	305	24.0	813	813	813	813					
	31' east of 1265+14.6	TO	1266+75.00	191	Var. 8' - 6'	161	161	161	161					
TOTALS						1796	1796	1796	1925	223	317	263	263	

PAVEMENT MARKING SCHEDULE

STATION TO STATION				POLYUREA PAVEMENT MARKING				TEMPORARY			NOTES	
				4 INCH WHITE	4 INCH SKIP-DASH YELLOW	6 INCH WHITE	24 INCH WHITE	4 INCH	6 INCH	24 INCH		
				FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT		
IL 13 (MAIN ST) - STA. 1262+53 TO STA. 1264+93												
	1262+51.0	TO	1264+78.0		57				57			MAINLINE
LT	1262+85.0	TO	1264+65.0	180					180			PARKING LANE
	1262+81.0	TO	1262+87.0			89				89		CROSSWALK
	1264+84.0	TO	1264+90.0			97				97		CROSSWALK
RT	1264+78.0						18				18	STOP BAR
IL 13 (WATER ST) - STA. 1265+14.6 TO STA. 1265+50												
	144' EAST OF 1265+14.5	TO	1266+75.0		70				70			MAINLINE
	144' EAST OF 1265+14.5					98				98		CROSSWALK
	1266+62	TO	1266+68			74				74		CROSSWALK
SUB-TOTALS				180	127	358	18		307	358	18	
TOTALS						307	358	18	307	358	18	

*FAP 42/841