

SUMMARY OF QUANTITIES

CODE #	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
* 40600200	BITUMINOUS MATERAILS (PRIME COAT)	TON	16
40600300	AGGREGATE (PRIME COAT)	TON	15
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	11
* 40600990	TEMPORARY RAMP	SQ YD	86
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	3495
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	3164
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	14
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	37668
44201789	CLASS D PATCHES, TYPE II 12"	SQ YD	60
48101200	AGGREGATE SHOULDERS, TYPE B	TON	500
60255500	MANHOLES TO BE ADJUSTED	EACH	2
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	6
* 60266100	VALVE VAULTS TO BE RECONSTRUCTED	EACH	3
* 60406100	FRAME AND LIDS, TYPE 1, CLOSED LID	EACH	3
67100100	MOBILIZATION	L SUM	1
* 70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	5303
* 70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2060
^ 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	996
^ 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	28185

CODE #	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
^ 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	2217
^ 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	224
^ 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	103
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1
^ 72000100	SIGN PANEL - TYPE 1	SQ FT	157
^ 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	191
^ 73100100	BASE FOR TELESCOPING STEEL SIGN SUPPORT	EACH	17

* - SPECIAL PROVISION

^ - SPECIALITY ITEM

NOTE - CONSTRUCTION FUND TYPE CODE (1000)

FILE NAME	USER NAME - \$USERS	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
\$FILES		DRAWN -	REVISED -			5345	09-00139-01-RS	DEKALB	19	3
	PLOT SCALE - \$SCALES	CHECKED -	REVISED -		SCALE:					
	PLOT DATE - \$DATES	DATE -	REVISED -		SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT	CONTRACT NO. 87400