

SUMMARY OF QUANTITIES

CODE No.	ITEM	UNIT	QUANTITY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	286
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	18
20200100	EARTH EXCAVATION	CU YD	2756
20300100	CHANNEL EXCAVATION	CU YD	580
20400800	FURNISHED EXCAVATION	CU YD	544
20700220	POROUS GRANULAR EMBANKMENT	CU YD	240
^ 25001000	SEEDING, CLASS 2 (SPECIAL)	ACRE	0.8
^ 25001100	SEEDING, CLASS 3 (SPECIAL)	ACRE	0.27
25100630	EROSION CONTROL BLANKET	SQ YD	1207
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	214
28000300	TEMPORARY DITCH CHECKS	EACH	45
28000400	PERIMETER EROSION BARRIER	FOOT	2740
28000500	INLET AND PIPE PROTECTION	EACH	1
28100207	STONE RIPRAP, CLASS A4	TON	1033
28200200	FILTER FABRIC	SQ YD	1610
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	2164
48101200	AGGREGATE SHOULDERS, TYPE B	TON	320
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1
50200100	STRUCTURE EXCAVATION	CU YD	424
50300225	CONCRETE STRUCTURES	CU YD	44.6
50300255	CONCRETE SUPERSTRUCTURE	CU YD	173.7
50300260	BRIDGE DECK GROOVING	SQ YD	316
50300280	CONCRETE ENCASEMENT	CU YD	5.2
50300300	PROTECTIVE COAT	SQ YD	424
50400735	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE BULB T-BEAMS 63"	FOOT	500
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	37450
51201800	FURNISHING STEEL PILES HP14X73	FOOT	256
51202305	DRIVING PILES	FOOT	136
51203800	TEST PILE STEEL HP14X73	EACH	1
51204650	PILE SHOES	EACH	4
^ 51204900	STEEL SHEET PILING	SQ FT	544
51500100	NAME PLATES	EACH	1
54200229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	56

^ - SEE SPECIAL PROVISIONS

SUMMARY OF QUANTITIES

CODE No.	ITEM	UNIT	QUANTITY
^ 54215545	METAL END SECTIONS 10"	EACH	5
^ 54215559	METAL END SECTIONS 24"	EACH	2
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	102
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	4
60108900	PIPE UNDERDRAINS, PERFORATED CORRUGATED STEEL PIPE 10"	FOOT	161
^ 60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	200
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4
* ^ 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	3
63200310	GUARDRAIL REMOVAL	FOOT	439
^ 67100100	MOBILIZATION	L SUM	1
* ^ 78200405	GUARDRAIL MARKERS	EACH	8
* ^ 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4
X0301512	GUARDRAIL AGGREGATE EROSION CONTROL	TON	97
^ XX004565	GROUTED RIPRAP	SQ YD	1140
* ^ XX005705	STEEL PLATE BEAM GUARD RAIL, SHORT RADIUS, 10'	FOOT	12.5
^ Z0027800	GEOTECHNICAL FABRIC	SQ YD	200
^ Z0065000	SETTING PILES IN ROCK	EACH	5

^ - SEE SPECIAL PROVISIONS

\* SPECIALTY ITEMS

FILE NAME = 070373-sh-t-summary.dgn	USER NAME =	DESIGNED - L.F.S. DRAWN - TWK	REVISED - REVISED -
	PLOT SCALE =	CHECKED - S.W.M.	REVISED - 02/02/09
	PLOT DATE = 2/2/2009	DATE - 10/17/08	REVISED -

STATE OF ILLINOIS  
WOODFORD COUNTY HIGHWAY DEPARTMENT

**HLR** HAMPTON, LENZINI & RENWICK, INC.  
CIVIL & STRUCTURAL ENGINEERS  
LAND SURVEYORS

SCALE: SHEET NO. OF SHEETS STA. TO STA.

SUMMARY OF QUANTITIES

T.R.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
50	05-08145-00-BR	WOODFORD	47	3
METAMORA R.D.		CONTRACT NO. 89448		
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				