

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

LOCATION OF WORK				CONSTRUCTION TYPE CODE: SFTY				
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	FIRST / SOUTH STREET SIDEWALK	ZIMMERMAN DRIVE SHARED PATH	ADA RAMP UPGRADE	BROOKSIDE GLEN SCHOOL SIDEWALK	VARIOUS SIDEWALK REPAIR
35100500	AGGREGATE BASE COURSE, TYPE A 6"	SQ YD	1,924		1,924			
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	728		728			
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	272		272			
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	13,568	8,492	773	824	711	2,768
42400800	DETECTABLE WARNINGS	SQ FT	160	64		96		
44000300	CURB REMOVAL	FOOT	20	20				
44000400	GUTTER REMOVAL	FOOT	119	23		96		
44000600	SIDEWALK REMOVAL	SQ FT	3,271			503		2,768
54200430	PIPE CULVERTS, TYPE 1 RCCP 15"	FOOT	12		12			
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	2		2			
550B0030	STORM SEWERS, CLASS B, TYPE 1 8"	FOOT	10				10	