

SIGN SCHEDULE					
STATION	LOCATION	TYPE	APPROXIMATE SIZE	SIGN PANEL TYPE 1 72000100 (SQ FT)	WOOD SIGN SUPPORT 73000100 (FOOT)
11+12	RT	W16-1	1.5 x 2	3	11
12+85	LT	W16-1	1.5 x 2	3	11
15+01	RT	W16-1	1.5 x 2	3	11
16+80	LT	W16-1	1.5 x 2	3	11
19+00	RT	W16-1	1.5 x 2	3	11
20+79	LT	W16-1	1.5 x 2	3	11
22+94	RT	W16-1	1.5 x 2	3	11
24+77	LT	W16-1	1.5 x 2	3	11
26+98	RT	W16-1	1.5 x 2	3	11
28+67	LT	W16-1	1.5 x 2	3	11
32+23	LT	W16-1	1.5 x 2	3	11
TOTALS				33	121

PAVEMENT MARKING SCHEDULE						
STATION	STATION	SHORT-TERM PAVT MKING 70300100 (FOOT)	WORK ZONE PAVT MK REM 70301000 (SQ FT)	PAINT PAVT MK LINE 4 78001110 (FOOT)	PAINT PAVT MK LINE 6 78001130 (FOOT)	PAINT PAVT MK LINE 12 78001150 (FOOT)
10+21	33+27	696	77			
10+18	10+40				80	13
10+33	13+62			90		
13+54	14+34				283	
14+25	17+60			90		
17+53	18+31				287	
18+24	21+55			90		
21+45	22+27				224	
22+18	25+50			90		
25+42	26+29				316	
26+15	29+49			90		
26+57	27+19			94		
28+19	29+25			154		
29+37	30+18				261	
30+09	33+07			80		
30+45	30+67			38		
31+35	32+85			214		
32+98	33+27				110	13
TOTAL		696	77	1,030	1,561	26

CURB & GUTTER SCHEDULE				
STATION	STATION	OFFSET	COMB CURB & GUTTER REMOVAL 44000500 (FOOT)	COMB CC&G TB6.24 60605000 (FOOT)
26+17	26+27	13' LT	10	10
TOTAL			10	10

PATCHING SCHEDULE						
STATION	LOCATION	APPROXIMATE SIZE	CLASS C PATCHES, TY 1, 10 INCH 44201349 (SQ YD)	CLASS C PATCHES, TY 2, 10 INCH 44201353 (SQ YD)	CLASS C PATCHES, TY 3, 10 INCH 44201357 (SQ YD)	CLASS C PATCHES, TY 4, 10 INCH 44201359 (SQ YD)
30+08	RT	10 x 55				62
31+71	RT	5 x 8	5			
31+77	RT	7 x 20			16	
31+82	LT	7 x 14		11		
33+22	RT	9 x 23			23	
TOTALS			5	11	39	62

PAVEMENT SCHEDULE						
STATION	STATION	BIT MATLS PR CT 40600100 (GAL)	AGG PR CT 40600300 (TON)	HOT-MIX ASPHALT SC "D" N70 40603340 (TON)	HMA SURFACE REMOVAL 2 1/2 44000159 (SQ YD)	STRIP REF CR CON TR 44300200 (FOOT)
10+21	33+27	635	13	1,185	8,465	2,306
10+27, 10.5' LT	25+27, 10.5' LT					1,500
10+58, 10.5' RT	25+60, 10.5' RT					1,502
21+40, 15.3' LT	22+00, 14.7' LT					60
25+27, 10.5' LT	26+20, 10.0' LT					93
25+60, 10.5' RT	26+48, 10.0' RT					88
26+20, 10.0' LT	32+73, 10.0' LT					653
26+48, 10.0' RT	33+16, 10.0' RT					668
29+18, 12.1' LT	30+12, 12.0' LT					94
TOTAL		635	13	1,185	8,465	6,964

FILE NAME = 853MN01.DWG	USER NAME = BILL TINDALL	DESIGNED: BET 2009-02-25	REVISED -
		DRAWN: BET 2009-02-25	REVISED -
PLOT SCALE = 6" = 1'		CHECKED: BSH 2009-02-25	REVISED -
PLOT DATE = 2009-02-25		DATE: SMK 2009-02-25	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULES

F.A.U. RTE 8853	SECTION 08-00060-00-RS	COUNTY MADISON	TOTAL SHEETS 7	SHEET NO. 3
CONTRACT NO. 97373				
FED. ROAD DIST. NO. 8 ILLINOIS FED. AID PROJECT				