

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9024	07-00187-02-RP	MADISON	111	17
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO. 07376				

### PAVING SCHEDULE

LOCATION	PROCESSING MODIFIED SOIL 12 IN (SQ YD)	LIME (TON)	BIT MATL PR CT (GALLON)	SUB BASE GRANULAR MATERIAL, TYPE A (TON)	HOT-MIX ASPHALT SURFACE COURSE MIX C, N70 (TON)	HOT-MIX ASPHALT BINDER COURSE IL-19, N70 (TON)	CLASS D PATCHES TYPE I 11" (SQ YD)	AGGREGATE SHOULDERS TYPE B (TON)
MOCKINGBIRD LANE								
STA. 116+92.00 TO STA. 117+20.76	81.1	2.0	19.5	18.5	8.0	16.0		1.41
STA. 117+20.76 TO STA. 148+42.53	12136.0	300.4	2422.3	2485.6	1085.2	2170.4		
WHIPPOORWILL LANE								
STA. 10+58.02 TO STA. 22+03.21							829.8	
<b>TOTAL</b>	<b>12217</b>	<b>302</b>	<b>2442</b>	<b>2504</b>	<b>1093</b>	<b>2186</b>	<b>830</b>	<b>1</b>

### PROTECTIVE COAT SCHEDULE

LOCATION	PROTECTIVE COAT AREA (SQ YD)
MOCKINGBIRD LANE	
COMBINATION CURB AND GUTTER, B-6.24	2101.0
DRIVEWAY PAVEMENT	2112.0
4" PCC SIDEWALK	2750.3
<b>TOTAL</b>	<b>6963</b>

### CURB REMOVAL SCHEDULE

LOCATION	CURB TYPE B (FOOT)
MOCKINGBIRD LANE	
STA. 119+40.74 - 30.04' RT TO STA. 119+40.72 - 34.60' RT	5
STA. 119+71.15 - 30.69' RT TO STA. 119+71.13 - 34.78' RT	4
STA. 127+40.79 - 29.79' RT TO STA. 127+40.75 - 47.53' RT	18
STA. 127+71.55 - 29.65' RT TO STA. 127+71.45 - 47.37' RT	18
STA. 137+65.01 - 34.11' RT TO STA. 137+64.76 - 53.93' RT	20
STA. 137+99.14 - 34.15' RT TO STA. 137+99.07 - 51.53' RT	18
STA. 141+76.35 - 27.73' LT TO STA. 141+80.95 - 39.86' LT	13
STA. 142+06.84 - 40.14' LT TO STA. 142+11.19 - 27.54' LT	14
<b>TOTAL</b>	<b>110</b>

### PAVEMENT MARKINGS

LOCATION	TYPE	THERMOPLASTIC PAVEMENT MARKINGS		PREFORMED PLASTIC PAVEMENT MARKINGS		
		4" YELLOW (FOOT)	6" WHITE (FOOT)	TYPE B		
				12" WHITE (FOOT)	24" WHITE (FOOT)	LETTERS & SYMBOLS (SQ FT)
MOCKINGBIRD LANE						
STA. 116+92.00 TO STA. 148+42.53						
	SKIP-DASH 10'-30'	788				
	STOP BARS			82	26	
	CROSSWALKS		491			
	RAILROAD CROSSING					61
	YIELD LINE					11
<b>TOTAL</b>		<b>788</b>	<b>491</b>	<b>82</b>	<b>26</b>	<b>72</b>


### SIGN SCHEDULE

LOCATION	LT / RT	PROPOSED OFFSET (FT)	DESCRIPTION	SIGN PANEL T1 (SQ FT)	METAL POSTS SIGN ASSEMBLY	
					TYPE A (FOOT)	TYPE B (FOOT)
MOCKINGBIRD LANE						
STA. 117+98.64	RT	18.58	R1-5L-1818	2.3	1 @ 12.0	
STA. 118+31.97	LT	28.58	R1-5L-1818	2.3	1 @ 12.0	
STA. 119+75.23	RT	34.32	R1-1-30	6.3		1 @ 13.5
STA. 121+00.00	LT	25.25	W10-1-30	6.3		1 @ 13.5
STA. 123+96.77	LT	25.24	R2-1-2430 / W9-12-2430	10.0		1 @ 15.0
STA. 123+96.77	RT	25.24	R2-1-2430 / W9-12-2430	10.0		1 @ 15.0
STA. 127+79.11	RT	25.43	R1-1-30	6.3		1 @ 13.5
STA. 128+82.30	RT	25.25	R2-1-2430 / W9-12-2430	10.0		1 @ 15.0
STA. 130+50.00	LT	25.25	R2-1-2430 / W9-12-2430	10.0		1 @ 15.0
STA. 138+07.00	RT	32.39	R1-1-30	6.3		1 @ 13.5
STA. 141+07.00	RT	34.10	R1-1-30	6.3		1 @ 13.5
STA. 141+12.03	LT	25.25	R2-1-2430	5.0		1 @ 13.5
STA. 141+73.26	LT	29.03	R1-1-30	6.3		1 @ 13.5
<b>TOTAL</b>				<b>87</b>	<b>24</b>	<b>155</b>

### EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION (CU YD)	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE(+) OR SHORTAGE(-) (CU YD)
ROADS AND DITCHES	6175	4631	354	4278
<b>TOTAL</b>	<b>6175</b>	<b>4631</b>	<b>354</b>	<b>4278</b>

NOTE: BASED ON 25% SHRINKAGE

 <b>Juneau Associates, Inc. P.C.</b> CONSULTING ENGINEERS AND LAND SURVEYORS 2100 State Street, P.O. Box 1323 Granite City, Illinois 62040 Phone: (618) 937-1400 / (618) 932-8334 Fax: (618) 932-5941 100 North Research Drive Granite City, Illinois 62040 Phone: (618) 938-0500 / (618) 938-0800 Fax: (618) 938-0941	<b>QUANTITY SCHEDULES</b> F.A.U. ROUTE 9024 MOCKINGBIRD LANE GRANITE CITY, ILLINOIS SECTION NO. 07-00187-02-RP								
	<b>REVISIONS</b> <table border="1"> <thead> <tr> <th>NO.</th> <th>DATE</th> <th>BY</th> <th>REMARKS</th> </tr> </thead> <tbody> <tr> <td> </td> <td> </td> <td> </td> <td> </td> </tr> </tbody> </table>		NO.	DATE	BY	REMARKS			
NO.	DATE	BY	REMARKS						
SCALE: NOT TO SCALE		SHEET NO. 17							
DWG. NO. E050210		DGN. NAME: MCOMSCH OF 111 SHTS							

DATE	BY	SURVEYED	PLOTTED	NOTE BOOK	TEMPLATE	AREAS CHECKED

DATE	BY	ORIGINAL SURVEYED	PLOTTED	NOTE BOOK	TEMPLATE	AREAS CHECKED