SUMMARY OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	QUANTITY	AS-BUILT QUANTITY
AR150510	ENGINEER'S FIELD OFFICE	L.S.	1	
AR150530	TRAFFIC MAINTENANCE	L.S.	1	
AR150540	HAUL ROUTE	L.S.	1	
AR201661	CLEAN & SEAL BITUMINOUS CRACKS	L.F.	5,000	
AR401610	BITUMINOUS SURFACE COURSE	TON	3,840	
AR401630	BITUMINOUS SURFACE TEST SECTION	EACH	1	
AR401640	BITUMINOUS PAVEMENT GROOVING	S.Y.	13,867	
AR401650	BITUMINOUS PAVEMENT MILLING	S.Y.	16,000	
AR603510	BITUMINOUS TACK COAT	GAL.	4,000	
AR620520	PAVEMENT MARKING-WATERBORNE	S.F.	13,000	
AR620525	PAVEMENT MARKING-BLACK BORDER	S.F.	1,440	

INDEX TO SHEETS

SHEET NO.	SHEET DESCRIPTION
1	COVER SHEET
2	SUMMARY OF QUANTITIES AND INDEX TO SHEETS
3	PROPOSED SAFETY PLAN
4	PROPOSED PAVEMENT PREPARATION PLAN
5	PROPOSED CONSTRUCTION PLAN
6	EXISTING AND PROPOSED TYPICAL SECTIONS
7	PROPOSED PLAN AND PROFILE – STA. 364+00 TO STA. 378+00
8	PROPOSED MARKING PLAN
9	PROPOSED GROOVING PLAN
10	PROPOSED CROSS-SECTIONS – STA. 365+90 TO STA. 367+00
11	PROPOSED CROSS-SECTIONS – STA. 367+50 TO STA. 369+00
12	PROPOSED CROSS-SECTIONS – STA. 369+50 TO STA. 371+00
13	PROPOSED CROSS-SECTIONS – STA. 371+50 TO STA. 373+00
14	PROPOSED CROSS-SECTIONS – STA. 373+50 TO STA. 375+00
15	PROPOSED CROSS-SECTIONS – STA. 375+50

DATE	REVISION	BY

DECATUR AIRPORT

DECATUR, ILLINOIS

IL PROJ.: DEC-3911 A.I.P. PROJ.: 3-17-0033-2_

HEI Project No. 08A0099D 0800
Filename R-002FLP.DWG
Scale N/A
Date 04/17/09

LAYOUT	MLH	01/23/09
DRAWN	MLH	01/26/09
REVIEWED	RAW	01/30/09

HANSON

© Copyright: Hanson Professional Services Inc. 2009
Hanson Professional Services Inc.
1525 South Sixth Street
Springfield, Illinois 62703-2896
www.hanson-inc.com
Offices Nationwide

RECONSTRUCT 960 FEET OF RUNWAY 6-24

SUMMARY OF QUANTITIES AND INDEX TO SHEETS

MAY 05, 2009 8:40 AM HARRIO1115
I:\08J0ES\08A0099D\CADD\AIRPORT\SHEET\R-002FLP.DWG