(2) PROPOSED AR603: BITUMINOUS TACK COAT (0.05 GAL/SYD)

(3) PROPOSED AR603: BITUMINOUS TACK COAT (0.20 GAL/SYD)

(4) EXISTING AR401: BITUMINOUS SURFACE COURSE - 4"

(5) EXISTING AR201: BITUMINOUS BASE COURSE - 2"-3"

(6) EXISTING AR401: BITUMINOUS SURFACE COURSE - 2"

(7) EXISTING AR201: BITUMINOUS BASE COURSE - 0"-10" VARIABLE DEPTH

(8) EXISTING AR401: BITUMINOUS SURFACE COURSE - 4"

(9) EXISTING AR501: PCC PAVEMENT - 9"

(10) EXISTING AR208: AGGREGATE SUBBASE COURSE - 8"

(1) EXISTING GROUND

BITUMINOUS MILLING - VARIABLE 3" TO 5"

10'-0" RUNWAY PAVEMENT EARTH SHOULDER TO BE RESHAPED, FERTILIZED, AND SEEDED IN DISTURBED AREAS-EXISTING GROUND

DETAIL 1 EARTH SHOULDER

NOTE:
IT IS NOT ANTICIPATED THAT THE EARTH SHOULDERS WILL NEED REGRADING FOLLOWING PAVING OPERATIONS. IF HOWEVER, THE DISTANCE BETWEEN THE PAVEMENT AND THE EXISTING GROUND EXCEEDS 1-1/2" AT PAVEMENT EDGE, THE CONTRACTOR SHALL ADD OR REMOVE MATERIAL AS REQUIRED TO SHAPE THE EARTH SHOULDERS TO CONFORM TO THE EARTH SHOULDER DETAIL. THE CONTRACTOR WILL REGRADE, SEED AND FERTILIZE THE DISTURBED EARTH SHOULDER. FERTILIZING AND SEEDING SHALL BE ACCOMPLISHED IN ACCORDANCE TO SPECIFICATION ITEM AR901510.

NO ADDDITIONAL PAYMENT FOR THE GRADING AND SEEDING ITEM WILL BE MADE TO THE CONTRACTOR. PAYMENT FOR THE WORK SHALL BE INCLUDED IN THE BID AMOUNT PER TON FOR THE BITUMINOUS SURFACE COURSE.


IN ADDITION, ANY TURF AREAS OUTSIDE THE PROJECT LIMITS DISTURBED BY THE CONTRACTOR WILL BE RESHAPED, FERTILIZED AND SEEDED ACCORDING TO THE ABOVE PARAGRAPH.




HANSON

RECONSTRUCT 960 FEET OF RUNWAY 6-24

6



RUNWAY 6-24 STA. 365+90 TO STA. 375+50



RUNWAY 6-24 STA. 365+90 TO STA. 375+50