

REVISIONS

NUMBER	BY	DATE

0 1 2
 THIS BAR IS EQUAL TO 2"
 AT FULL SCALE (34X22).
 PLOT 1

SUMMARY OF QUANTITIES

ITEM	DESCRIPTION	UNIT	QUANTITY
AR401900	REMOVE BITUMINOUS PAVEMENT	SY	90
AR501505	5" PCC PAVEMENT	SY	90
AR605540	CLEAN AND SEAL JOINTS	LF	71,100
AR605541	CLEAN AND SEAL CRACKS	LF	330
AR801954	L-893 LIGHTED RUNWAY CLOSURE MARKER	EA	2
AR801964	PCC SPALL REPAIR	SF	500
AR801970	LOW PROFILE LIGHTED BARRICADE	EA	50

**MIDAMERICA ST. LOUIS AIRPORT
 ST. CLAIR COUNTY, ILLINOIS**

RUNWAY AND TAXIWAY JOINT REPAIR

ONE MEMORIAL DRIVE, SUITE 500
 ST. LOUIS, MO 63102
 (314) 438-5500



**IL PROJECT: BLV-3886
 AIP PROJ: 3-17-0146-XX**

FILE: 02_QUANTITIES.dwg

DESIGN BY: LEW

DRAWN BY: ASA

CHECKED BY: BWG

APPROVED BY: BWG

DATE: APRIL 17, 2009

JOB No: 09098-01

**SUMMARY OF
 QUANTITIES**