	SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
	CODE NO	ITEM	UNIT		100% STATE 0005				
*	78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	934	934				
*	78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	228	228				
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	512	512				
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	148	148				
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	461	461				
*	88600600	DETECTOR LOOP REPLACEMENT	FOOT	854	854				
	X0326767	PROFILE DIAMOND GRINDING CONCRETE PAVEMENT	SQ YD	52772	52772				
	X0327695	PRECAST CONCRETE PAVEMENT SLABS 9 3/4"	SQ FT	9075	9075				
	X4423015	DOWEL BARS 1 1/2" RETROFIT	EACH	1513	1513				
	X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	600	600				
	Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	757	757				
	Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4				

* SPECIALTY ITEMS

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT							

Rev. 5-29-15

FILE NAME = c:\pw_work\pwidot\pancepl\d410940\D106715-sht-plan.dgn	USER NAME = PancePL	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
Default	PLOT DATE = 4/7/2015	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

WB IL 62 (ALGONQUIN ROAD)-PENNY ROAD TO WEST OF ROSELLE ROAD
SUMMARY OF QUANTITIES

SCALE: | SHEET OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
339	116(R&R-3)PCC-PP-1	COOK	45	4

CONTRACT NO. 62A11

ILLINOIS FED. AID PROJECT