

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				100% STATE	
				ROADWAY 0005	RURAL
40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUNDS	14951	14951	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	9.8	9.8	
67100100	MOBILIZATION	L SUM	1	1	
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1	
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	16	16	
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1	
70100815	TRAFFIC CONTROL AND PROTECTION, STANDARD 701446	L SUM	1	1	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2	2	
70300520	PAVEMENT MARKING TAPE, TYPE III, 4"	FOOT	9247	9247	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	3082	3082	
* 78008320	POLYUREA PAVEMENT MARKING, TYPE II, LINE 5"	FOOT	9247	9247	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2318	2318	
78300100	PAVEMENT MARKING REMOVAL	SO FT	27740	27740	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	2318	2318	
X0326218	FIBER-MODIFIED ASPHALT CRACK SEALING	FOOT	92467	92467	

* SPECIALTY ITEM

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				100% STATE	
				ROADWAY 0005	RURAL
X7010410	SPEED DISPLAY TRAILER	CAL MO	2	2	
Z0063804	MICRO-SURFACING, SINGLE PASS, TYPE II, MIXTURE D	SO YD	33223	33223	

REVIS 6-1-15

* 06 PAVT PRESERVATION 2015

FILE NAME *	USER NAME * branhama	DESIGNED -	REVISED -
S:\CONTRACTS\2015-2016\72478-PAV 55 (1 55) - 06	PAVT PRES 2015-SAND\PLANS\ALL SHEETS.dgn	DRAWN -	REVISED -
	PLOT SCALE * 1/8"=1'-0"	CHECKED -	REVISED -
Default	PLOT DATE * Apr-03-2015 02:33:05PM	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	*	SANGAMON	6	3
CONTRACT NO. 72478			ILLINOIS FED. AID PROJECT	

MAINLINE											
LOCATION STA. TO STA.		LENGTH	PAVEMENT MARKING TAPE TYPE III 4"	WORK ZONE PAVEMENT MARKING REMOVAL	POLYUREA PAVEMENT MARKING TYPE II, 5"	RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	FIBER-MODIFIED ASPHALT CRACK SEALING	MICRO-SURFACING SINGLE PASS TYPE II MIXTURE D	BITUMINOUS MATERIALS (PRIME COAT)	MIX FOR CRACKS, JOINTS & FLANGEWAYS
		FT	FT	SO FT	FT	EACH	EACH	FT	SO YD	POUNDS	TDN
NORTHBOUND											
285+00.00	366+00.68	8100.68	810	270	810	204	204	8100	2700	1215	.8
366+00.68	369+37.72	BRIDGE OMISSION									
369+37.72	514+51.60	14513.88	1451	484	1451	364	364	14513	4838	2177	1.4
514+51.60	517+28.60	BRIDGE OMISSION									
517+28.60	549+76.71	3248.11	325	108	325	82	82	3248	1083	488	.3
549+76.71	552+36.38	BRIDGE OMISSION									
552+36.38	755+62.82	20326.44	2033	678	2033	508	508	20326	6775	3049	2.0
NORTHBOUND											
285+00.00	367+29.80	8229.80	823	274	823	206	206	8229	2743	1234	.8
367+29.80	370+72.90	BRIDGE OMISSION									
370+72.90	514+51.60	14378.70	1438	479	1438	360	360	14378	4793	2157	1.4
514+51.60	517+28.60	BRIDGE OMISSION									
517+28.60	550+70.32	3341.72	334	111	334	84	84	3341	1114	501	.3
550+70.32	552+29.99	BRIDGE OMISSION									
552+29.99	755+62.82	20332.83	2033	678	2033	510	510	20332	6777	3050	2.0
I-55 AND EXIT 88		1800.00						1800	600	270	.2
I-55 AND EXIT 83		1800.00						1800	600	270	.2
I-55 AND EXIT 82		1800.00						1800	600	270	.2
I-55 AND EXIT 80		1800.00						1800	600	270	.2
TOTAL			9247	3082	9247	2318	2318	99667	33223	14951	9.8

⚠️ REVISED SHEET 6-1-15

FILE NAME *	USER NAME * brachonns	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				* D6 PAVT PRESERVATION 2015			
S:\CONTRACTS\2015\2015-PAV PRES 2015-SANGAMON-SHEETS.dgn	PAV PRES 2015-SANGAMON-SHEETS.dgn	DRAWN -	REVISED -						P.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS
Default	PLOT SCALE * 100.0000 / in.	CHECKED -	REVISED -		55	.	SANGAMON	6	5			
	PLOT DATE * 5/21/2015	DATE -	REVISED -		CONTRACT NO. 72H78				ILLINOIS FED. AID PROJECT			