

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
20100500	TREE REMOVAL, ACRES	ACRE	0.3
20200100	EARTH EXCAVATION	CU YD	5,471
20300100	CHANNEL EXCAVATION	CU YD	7,341
28000305	TEMPORARY DITCH CHECKS	FOOT	133
28000400	PERIMETER EROSION BARRIER	FOOT	188
28100109	STONE RIPRAP, CLASS A5	SQ YD	2,218
28200200	FILTER FABRIC	SQ YD	2,218
35100700	AGGREGATE BASE COURSE, TYPE A 8"	SQ YD	1,158
40200100	AGGREGATE SURFACE COURSE, TYPE A	TON	16
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	20
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	436
40300300	BITUMINOUS MATERIALS (COVER AND SEAL COAT)	GALLON	1,644
40300500	COVER COAT AGGREGATE	TON	34
40300600	SEAL COAT AGGREGATE	TON	18
44000100	PAVEMENT REMOVAL	SQ YD	976
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1
50200100	STRUCTURE EXCAVATION	CU YD	197
50300225	CONCRETE STRUCTURES	CU YD	123.4
50300260	BRIDGE DECK GROOVING	SQ YD	654
50300300	PROTECTIVE COAT	SQ YD	701
50400605	PRECAST PRESTRESSED CONCRETE DECK BEAMS (33" DEPTH)	SQ FT	6,300
50800105	REINFORCEMENT BARS	POUND	6,800
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	41,620
20013798	CONSTRUCTION LAYOUT	LSM	1

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
50800515	BAR SPLICERS	EACH	264
50800530	MECHANICAL SPLICERS	EACH	96
* 50901050	STEEL RAILING, TYPE SM	FOOT	424
51201800	FURNISHING STEEL PILES HP14X73	FOOT	280
51202305	DRIVING PILES	FOOT	280
51203800	TEST PILE STEEL HP 14X73	EACH	1
51204650	PILE SHOES	EACH	12
51500100	NAME PLATES	EACH	1
51602000	PERMANENT CASING	FOOT	102
51603000	DRILLED SHAFT IN SOIL	CU YD	37.1
51604000	DRILLED SHAFT IN ROCK	CU YD	41.9
59300100	CONTROLLED LOW STRENGTH MATERIAL	CU YD	65.7
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	125
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	3
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	3
* 63200310	GUARDRAIL REMOVAL	FOOT	95
66600105	FURNISHING AND ERECTING R.O.W. MARKERS	EACH	8
67100100	MOBILIZATION	L SUM	1
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	10
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	3
X2501000	SEEDING, CLASS 2 (SPECIAL)	ACRE	1.7
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	701
* X6310188	TRAFFIC BARRIER TERMINAL, TYPE 6A (MODIFIED)	EACH	1
Δ 20076600	TRAINEES	HOURL	1,000
Δ 20076604	TRAINEES TRAINING PROGRAM GRADUATE	HOURL	1,000

* SPECIALTY ITEMS
Δ 0042