

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE 0005
20101400	NITROGEN FERTILIZER NUTRIENT	POUND	25.00	25.00
20101500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	25.00	25.00
20101600	POTASSIUM FERTILIZER NUTRIENT	POUND	25.00	25.00
20200100	EARTH EXCAVATION	CU YD	2.00	2.00
21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	1,452.00	1,452.00
25000210	SEEDING, CLASS 2A	ACRE	0.30	0.30
25100630	EROSION CONTROL BLANKET	SQ YD	1,452.00	1,452.00
28000500	INLET AND PIPE PROTECTION	EACH	12.00	12.00
40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	20,500.00	20,500.00
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	20.00	20.00
40600982	HOT MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	330.00	330.00
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	3,900.00	3,900.00
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3,000.00	3,000.00
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5"	SQ FT	300.00	300.00
42400800	DETECTABLE WARNINGS	SQ FT	48.00	48.00
44000100	PAVEMENT REMOVAL	SQ YD	100.00	100.00
44000165	HOT-MIX ASPHALT SURFACE REMOVAL, 4"	SQ YD	30,100.00	30,100.00
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	40.00	40.00
44000600	SIDEWALK REMOVAL	SQ FT	300.00	300.00
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	6.00	6.00
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	127.00	127.00
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	94.00	94.00
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	457.00	457.00
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	4,600.00	4,600.00
48101498	AGGREGATE SHOULDER, TYPE B 4"	SQ YD	300.00	300.00

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE 0005
60266600	VALVE BOXES TO BE ADJUSTED	EACH	1.00	1.00
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	40.00	40.00
* 63000009	STEEL BEAM GUARDRAIL, TYPE B, 9 FOOT POSTS	FOOT	1,406.00	1,406.00
* 63100041	TRAFFIC BARRIER TERMINAL, TYPE 1B	EACH	2.00	2.00
* 63200310	GUARDRAIL REMOVAL	FOOT	1,406.00	1,406.00
67100100	MOBILIZATION	L SUM	1.00	1.00
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1.00	1.00
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1.00	1.00
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1.00	1.00
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2.00	2.00
70300100	SHORT TERM PAVEMENT MARKING	FOOT	6,000.00	6,000.00
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2,000.00	2,000.00
* 78000100	THERMO PAVEMENT MARKING-LETTERS AND SYMBOLS	SQ FT	567.00	567.00
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	20,530.00	20,530.00
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,965.00	1,965.00
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	165.00	165.00
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	356.00	356.00
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	164.00	164.00
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	100.00	100.00
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1,000.00	1,000.00
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	180.00	180.00
* 88600100	DETECTOR LOOP, TYPE 1	FOOT	50.00	50.00
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	4.00	4.00
X6350120	DELINEATOR REMOVAL	EACH	50.00	50.00
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	51.40	51.40
* Z0052550	REPAIR TRAFFIC BARRIER TERMINAL, TYPE 1 B	EACH	2.00	2.00

* SPECIALTY ITEMS

FILE NAME = N:\dgn\NA\NA527_RandallResurfacingSouth	USE NAME = .USER_	DESIGNED -	REVISED - 6/10/2015	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	sheet: NA527_03Summary of Quantities.dgn	CHECKED -	REVISED -		2505	15-00055-00-RS	KANE	22	3				
	PLOT SCALE = 1.00 ft / in.	DRAWN -	REVISED -		SCALE: NONE SHEET NO. 3 OF 22 SHEETS STA. TO STA.				CONTRACT NO. 61B41				
	PLOT DATE = 3/11/2015	CHECKED -	REVISED -		FED. ROAD DIST. NO. ILLINOIS FED. ID PROJECT								