

SUMMARY OF QUANTITIES

SP	SI	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONS. TYPE CODE 021 80% FEDERAL 20% LOCAL
		20200100	EARTH EXCAVATION	CU YD	135	135
		21101610	TOPSOIL FURNISH AND PLACE, 3"	SQ YD	550	550
	X	25000100	SEEDING, CLASS 1	Acre	0.02	0.02
	X	25200100	SODDING	SQ YD	450	450
		42001300	PROTECTIVE COAT	SQ YD	925	925
		42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	120	120
		42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQ FT	21,475	21,475
X		42400800	DETECTABLE WARNINGS	SQ FT	160	160
X		44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	150	150
X		44000600	SIDEWALK REMOVAL	SQ FT	21,550	21,550
		67100100	MOBILIZATION	L SUM	1	1
		70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1
		70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
X		X4240430	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH, SPECIAL	SQ FT	6,790	6,790
		Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	100	100

SI - DENOTES SPECIALTY ITEM

SP - DENOTES SPECIAL PROVISION HAS BEEN PROVIDED

Drawing file: W:\Projects\by_Village\Brookfield\12514280 - Side Routes to School\04_500.dwg Feb 16, 2015 - 11:12am



♦ Civil Engineers
 ♦ Municipal Consultants
 ♦ Established 1911

9333 Roosevelt Road
 Westchester, Illinois 60154-3780
 Phone: 708/965-6300
 Fax: 708/965-1212

DESIGNED -	BPS	REVISED -	6-2-15
DRAWN -	DMM	REVISED -	
CHECKED -	---	REVISED -	
DATE -	02/11/15	REVISED -	

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
---	14-00127-00-SW	COOK	16	4
FIELD BOOK NO. :		CONTRACT NO. 61B47		
FED. ROAD DIST. NO. 1		ILLINOIS FED. AID PROJECT		