

SUMMARY OF QUANTITIES				CONSTRUCTION CODE	
				100% STATE	
				BRIDGE	
				0047	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	081-0074	
50102400	CONCRETE REMOVAL	CU YD	14.8	14.8	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	14.6	14.6	
50300300	PROTECTIVE COAT	SQ YD	39.5	39.5	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1750	1750	
50800515	BAR SPLICERS	EACH	24	24	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	113	113	
67000400	ENGINEERING FIELD OFFICE, TYPE A	CAL MO	1	1	
67100100	MOBILIZATION	L SUM	1	1	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
70300904	PAVEMENT MARKING TAPE, TYPE IV 4"	FOOT	2,131	2131	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	312.5	312.5	
70400200	RELOCATION TEMPORARY CONCRETE BARRIER	FOOT	275	275	
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2,022	2022	
X0327980	PAVEMENT MARKING REMOVAL - WATER BLASTING	SQ FT	674	674	
X5060601	CONTAINMENT AND DISPOSAL OF NON-LEAD PAINT CLEANING RESIDUES NO. 1	L SUM	1	1	
X7030005	TEMPORARY PAVEMENT MARKING REMOVAL	SQ FT	711	711	
Z0010501	CLEANING AND PAINTING STEEL BRIDGE NO. 1	L SUM	1	1	
Z0001903	STRUCTURAL STEEL REMOVAL	POUND	580	580	
Z0001905	STRUCTURAL STEEL REPAIR	POUND	790	790	
70600250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE) TEST LEVEL 3	EACH	2	2	
70600350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE) TEST LEVEL 3	EACH	2	2	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	

\*= SPECIALTY ITEM

FILE NAME = #FILE#



USER NAME = #USER#  
 PLOT SCALE = #SCALE#  
 PLOT DATE = #DATE#

DESIGNED - AA  
 DRAWN - BP  
 CHECKED - OAO  
 DATE - 03-19-2020

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES  
 SCALE: SHEET OF SHEETS STA. TO STA.

F.A.P. RTE. 599  
 SECTION D2 BJR 2020-3  
 COUNTY ROCK ISLAND  
 TOTAL SHEETS 22  
 SHEET NO. 03  
 CONTRACT NO. 64P36  
 (ILLINOIS) FED. AID PROJECT

REVISED 6/03/2020 REVISED 5/28/20 REV. 5/12/20 REV. 5/5/20 REV. 4/21/20