

SUMMARY OF QUANTITIES

90% FED. / 10% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	WILL COUNTY													90% FED. / 10% STATE		
				CONSTRUCTION TYPE CODE													CITY OF JOLIET 100% JOLIET	RETAINING WALLS CULVERTS	VILLAGE OF SHOREWOOD 100% VOS
				ROADWAY IL-59 90% FED 10% STATE	ROADWAY I-55 90% FED 10% STATE	ROADWAY NB RAMP 90% FED 10% STATE	ROADWAY SB RAMP 90% FED 10% STATE	ROADWAY SEIL RD 90% FED 10% STATE	ROADWAY FRONTG RD 90% FED 10% STATE	BRIDGE IL59 NB EXIT RAMP OVER I-55	BRIDGE IL59 OVER DUPAGE RIVER	SIGNING	EXPRESSWAY LIGHTING 100% STATE	VILLAGE LIGHTING 100% VOS	TRAFFIC SIGNALS 90% FED 6.7% STATE 3.3% VOS				
				J000-2A	I000-2A	J000-2A	J000-2A	I000-2A	I000-2A	X271-2A	X081-2A	Y002-2A	Y030-1E	Y030-1E	Y031-1F	J000-2A	Y007	J000-2A	
28001000	AGGREGATE (EROSION CONTROL)	TON	24.7	4.7		6.0	7.0	4.7	2.3										
28100105	STONE RIPRAP, CLASS A3	SQ YD	27		9	9		9											
28100107	STONE RIPRAP, CLASS A4	SQ YD	210	96		28	24	62											
28100109	STONE RIPRAP, CLASS A5	SQ YD	73	73															
28200200	FILTER FABRIC	SQ YD	326	177		48	32	69											
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	404	235		169													
31200500	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4"	SQ YD	13,754			7,283	6,471												
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	1,524	1,524															
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	119						119										
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	571	310				261											
35501313	HOT-MIX ASPHALT BASE COURSE, 7 1/4"	SQ YD	94	94															
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	1,114	652				462											
40200900	AGGREGATE SURFACE COURSE, TYPE B	CU YD	170					170											
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1.0	0.7				0.3											
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	0.3	0.3															
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	32.1	32.1															
40600895	CONSTRUCTING TEST STRIP	EACH	8		2			4	2										
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	297	206				67	24										
40701861	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9"	SQ YD	7,173						7,173										
40701996	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 15 3/4"	SQ YD	5,846					5,846											
40702021	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 17"	SQ YD	7,149		7,149														
42000416	PORTLAND CEMENT CONCRETE PAVEMENT 9 3/4" (JOINTED)	SQ YD	43,621	31,579		6,355	5,687												
42001300	PROTECTIVE COAT	SQ YD	55,879	43,758	41	6,386	5,687	7											
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	425	249		176													
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	1,001	1,001															
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	1,245	1,245															
2 42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	30,534	30,534															
2 42400800	DETECTABLE WARNINGS	SQ FT	238	238															
44000100	PAVEMENT REMOVAL	SQ YD	49,358	23,120	4,653	4,858		5,470	11,257										
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	666	666															
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	6,313	5,605				708											

* DENOTES SPECIALTY ITEMS

"2" DENOTES FED = 0%, STATE = 50%, VOS = 50% - *6FTY-1B*

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI 55 AT FAP 338 ILLINOIS ROUTE 59
SECTION: (26, 26HB-1&114) R-2

SUMMARY OF QUANTITIES 2

SCALE: DRAWN BY: JB
DATE: 03/14/08 CHECKED BY: ACL

TENQ

TENQ & ASSOCIATES, INC.
ENGINEERING ARCHITECTURE PLANNERS
200 N. KETCHUM AVE. CHICAGO, IL 60601
TELEPHONE: 312.966.0000

A:\SU000963.DGN - \SU000963.DGN - ATTORNEY\KACG
 3-24-2008 10:37:49 T:\DOCUMENTS\19327905.DGN\ADGNS\SU000963.DGN
 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63

REV.