

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	URBAN		100% CITY	
			QUANTITY	Y003	Y003	Y003
C2007010	SHRUB, ROSA RADRAZZ (KNOCKOUT ROSE), CONTAINER GROWN, 3-GALLON	EACH	623	623		
C2009120	SHRUB, FORSYTHIA X INTERMEDIA HAPPY CENTENNIAL (HAPPY CENTENNIAL FORSYTHIA) 18" HEIGHT, CONTAINER	EACH	542	542		
A2005034	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 10' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	10	10		
C2003353	SHRUB, HEPTACODIUM MICRONOIDES (SEVEN SON FLOWER), 8' HEIGHT, BALLED AND BURLAPPED	EACH	12	12		
C2004738	SHRUB, PHYSOCARPUS OPULIFOLIUS 'SUMMER WINE' (SUMMER WINE COMMON NINEBARK), 2-1/2' HEIGHT, CONTAINER	EACH	222	222		
A2008418	TREE, ULMUS MORTON GLOSSY (TRIUMPH ELM), 3" CALIPER, BALLED AND BURLAPPED	EACH	10	10		
C2006013	SHRUB, RHUS COPALLINA VAR. LATIFOLIA MORTON (PRAIRIE FLAME SHINING SUMAC) 3' HEIGHT, CONTAINER	EACH	968	968		
X0325962	PERENNIAL PLANTS, ALLIUM BULBS	UNIT	58	58		
25000210	SEEDING, CLASS 2A	ACRE	0.79	0.79		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	72	72		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	72	72		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	72	72		
25000750	MOWING	ACRE	2.6	2.6		
25100630	EROSION CONTROL BLANKET	SQ YD	3,824	3,824		
28000510	INLET FILTERS	EACH	34	34		
42001300	PROTECTIVE COAT	SQ YD	317		317	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	2,384		2,384	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	136		136	
44000600	SIDEWALK REMOVAL	SQ FT	2,384		2,384	
56104600	WATER VALVES 2"	EACH	2		2	
56200900	WATER SERVICE LINE 2 1/2"	FOOT	380		380	
66400550	CHAIN LINK FENCE, 4' (SPECIAL)	FOOT	1,971		1,971	
67100100	MOBILIZATION	L SUM	1	0.8	0.2	
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	0.8	0.2	
* 78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	59		59	
* 78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	61		61	
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	501		501	
* 78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	70		70	
B2006320	TREE, SYRINGA RETICULATA IVORY SILK (IVORY SILK JAPANESE TREE LILAC), 2-1/2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	32	32		
B2006374	TREE, SYRINGA RETICULATA IVORY SILK (IVORY SILK JAPANESE TREE LILAC), 10' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	20	20		

CODE NO.	ITEM	UNIT	URBAN		100% CITY	
			QUANTITY	Y003	Y003	Y003
E2009001	VINE EUONYMUS FORTUNEI ^{VAR.} COLORATUS (PURPLE LEAF WINTERCREEPER), 1-QUART POT	EACH	2,150	2,150		
K0030400	PERENNIAL PLANTS, DAYLILIES	UNIT	23	23		
K0030450	PERENNIAL PLANTS, DAFFODIL BULBS	UNIT	86	86		
K0030470	PERENNIAL PLANT, ORNAMENTAL GRASS TYPE	UNIT	58	58		
X0301407	PERENNIAL PLANTS, GALLON POT	UNIT	63	63		
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	103	103		
X0325971	CAST-IN-PLACE DETECTABLE WARNING SURFACE	SQ FT	44		44	
X0325103	WATER METER IN VAULT, 2 INCH	EACH	2		2	
X0325104	WATER TAP, 2 INCH	EACH	2		2	
X0325105	IRRIGATION SYSTEM	SQ YD	46,875		46,875	
X0656300	PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	233		233	
X6065740	CONCRETE MEDIAN SURFACE, 5" (MODIFIED)	SQ FT	192		192	
XX000541	EXPLORATORY EXCAVATION	CU YD	18		18	
XX003710	BACKFLOW PREVENTER, 2"	EACH	2		2	
X0325970	SOIL CONDITIONER 3"	SQ YD	6,825		6,825	
XX006326	TYPE K COPPER PIPE 2"	FOOT	425		425	
XX104800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-V.12	FOOT	136		136	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1			
Z0076600	TRAINERS	HOUR				
X0325106	IRRIGATION ^{SYSTEM} FALL SHUT-DOWN	EACH	2		2	
X0325107	IRRIGATION ^{SYSTEM} SPRING START-UP	EACH	2		2	
K1003460	LANDSCAPE MAINTENANCE	CAL MO	12		12	
C2002950	SHRUB, FORSYTHIA X INTERMEDIA COURTAOUR (GOLDLOCKS FORSYTHIA) 18" HEIGHT, CONTAINER	EACH	284	284		
C2002949	SHRUB, FORSYTHIA X INTERMEDIA COURDIJAU (GOLDEN PEEP FORSYTHIA) 18" HEIGHT, CONTAINER	EACH	286	286		
X0325004	WEED CONTROL, PRE-EMERGENT HERBICIDE	GALLON	2		2	
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1		1	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1		1	

NP=Non-Participating
* - Specialty Items

BOWMAN, BARRETT & ASSOCIATES INC
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbainc.com



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
GATEWAY LANDSCAPING & IRRIGATION @ 35TH

SUMMARY OF QUANTITIES

SCALE: NONE
DATE: 03/13/07

DRAWN BY: JDC
CHECKED BY: ODM

Rev.

S00-1
12:00:52 AM
3/15/2008