## INDEX OF SHEETS

SHEET NO.	DESCRIPTION			STATE STANDARDS
1	TITLE SHEET		000001-05	STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS
2	INDEX OF SHEETS, STATE STANDARDS, AND GENERAL NO	TES	642001	SHOULDER RUMBLE STRIPS
3	SUMMARY OF QUANTITIES	3	701400-02	APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
4-24	ROADWAY PLANS		701401-04	LANE CLOSURE, FREEWAY/EXPRESSWAY
			701411-04	LANE CLOSURE, MULTILANE, AT ENTRANCE OR EXIT RAMP, FOR SPEEDS 245MPH
				andre de la companya de la companya La companya de la co
			701901	TRAFFIC CONTROL DEVICES

## GENERAL NOTES:

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 800-892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS FACILITIES. ( 48 HOUR NOTIFICATION IS REQUIRED)

THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES AND THE CITY OF CHICAGO AND THE VILLAGES OF STICKNEY, FOREST VIEW, SUMMIT, BEDFORD PARK, HODGKINS AND COUNTRYSIDE.

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.

BARRICADES: THE CONTRACTOR SHALL PROVIDE AND INSTALL TWO
(2) WEIGHTED SANDBAGS ON EACH TYPE I, TYPE II OR TYPE III BARRICADE
USED- ONE (1) WEIGHTED SAND BAG ACROSS EACH BOTTOM RAIL.

THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE ARTERIAL TRAFFIC CONTROL SUPERVISOR A MINIMUM OF 72 HOURS PRIOR TO BEGINNING WORK.

COUNTY TOTAL SHEETS NO.
COOK 24 2 SECTION REVISED -DESIGNED -I55 from Willow Springs Rd. to California Ave. FILE NAME = USER NAME = abreuah STATE OF ILLINOIS DRAWN REVISED 2007-046 I INDEX OF SHEETS STATE STANDARDS AND GENERAL NOTES PLOT SCALE = 50.0000 '/ IN. CHECKED REVISED **DEPARTMENT OF TRANSPORTATION** CONTRACT NO. 60D36 SCALE: 1" = 50' SHEET NO. OF SHEETS STA. PLOT DATE = 12/17/2007 DATE REVISED