

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
351	2008-001VB	COOK	579	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

CONTRACT NO. 60E10

CODE NO.	PAY ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE																	
				80% FEDERAL / 20% STATE							50% STATE 50% HARVEY	100% HARVEY									
				ROADWAY J000-2A	RAILROAD K000-5B	RR BRIDGE 016-2755 2819 & 2822 X631-5B	INTERMODAL BRIDGE 016-2820 & 2821 X781-2A	RETAINING WALL Y007	TRAFFIC SIGNAL PARK AVE. Y031-1F	TRAFFIC SIGNAL INTER- CONNECT Y031-1F	NEW SIDEWALK SFTY-1B	WATER- MAIN Y060	LIGHTING Y030-1E	TRAFFIC SIGNAL EVP EQUIP. Y031-3D							
20101200	TREE ROOT PRUNING	EACH	1	1																	
20200100	EARTH EXCAVATION	CU YD	3128		3128																
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	2332		2332																
20700220	POROUS GRANULAR EMBANKMENT	CU YD	9120			3621	3093	2406													
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	69					69													
20800150	TRENCH BACKFILL	CU YD	149.1		149.1																
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	660		660																
25000310	SEEDING, CLASS 4	ACRE	0.2		0.2																
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	18		18																
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	18		18																
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	18		18																
25100630	EROSION CONTROL BLANKET	SQ YD	660		660																
28000400	PERIMETER EROSION BARRIER	FOOT	3835		3835																
28000500	INLET AND PIPE PROTECTION	EACH	2	1	1																
28000510	INLET FILTERS	EACH	48	48																	
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	2400		2400																
35501300	HOT-MIX ASPHALT BASE COURSE, 4"	SQ YD	2400		2400																
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	158		158																
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	537		537																
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	269		269																
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	991		991																
42001700	FURNISH PROFILOGRAPH	L SUM	1	1																	
44000100	PAVEMENT REMOVAL	SQ YD	2986		2986																

- DENOTES SPECIALTY ITEM
- Y080
- △ SFTY-3N
- NON-PARTICIPATING

**URS** 100 S. WACKER DR., SUITE 500  
CHICAGO, ILLINOIS 60606  
TEL. (312) 939-1000  
FAX (312) 939-4198

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
US RTE 6 FROM LEXINGTON AVE TO FISK AVE

SUMMARY OF QUANTITIES

DATE 02/21/08  
DRAWN BY J.R.P.  
CHECKED BY M.R.F.