

CODE NO.	PAY ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE														
				80% FEDERAL / 20% STATE							50% STATE 50% HARVEY	100% HARVEY						
				ROADWAY	RAILROAD	RR BRIDGE 016-2755 2819 & 2822	INTERMODAL BRIDGE 016-2820 & 2821	RETAINING WALL	TRAFFIC SIGNAL PARK AVE.	TRAFFIC SIGNAL INTER- CONNECT	NEW SIDEWALK	WATER- MAIN	LIGHTING	TRAFFIC SIGNAL EVP EQUIP.				
J000-2A	K000-5B	X631-5B	X781-2A	Y007	Y031-1F	Y031-1F	SFTY-1B	Y060	Y030-1E	Y031-3D								
56400100	FIRE HYDRANTS TO BE MOVED	EACH	3	3														
56400820	FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX	EACH	2										2					
56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	5	5														
58000110	MEMBRANE WATERPROOFING (SPECIAL)	SQ FT	19736.5			19736.5												
58700300	CONCRETE SEALER	SQ FT	2141			2141												
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	2776.2			1092.7	708	975.5										
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	565					565										
60109582	PIPE UNDERDRAINS FOR STRUCTURES 6"	FOOT	2831			958	536	1337										
60206905	CATCH BASINS, TYPE C, TYPE 1 FRAME, OPEN LID	EACH	5		5													
60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	1	1														
60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	EACH	35	35														
60218300	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	2		2													
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2		2													
60250200	CATCH BASINS TO BE ADJUSTED	EACH	2	2														
60255500	MANHOLES TO BE ADJUSTED	EACH	17	17														
60260100	INLETS TO BE ADJUSTED	EACH	3	3														
60265700	VALVE VAULT TO BE ADJUSTED	EACH	8	8														
60500040	REMOVING MANHOLES	EACH	19	19														
60500050	REMOVING CATCH BASINS	EACH	17	17														
60500060	REMOVING INLETS	EACH	19	17	2													
60500105	FILLING MANHOLES	EACH	6	6														

- DENOTES SPECIALTY ITEM
- Y080
- △ SFTY-3N
- NON-PARTICIPATING

URS 100 S. WACKER DR., SUITE 500
CHICAGO, ILLINOIS 60606
TEL. (312) 939-1000
FAX (312) 939-4198

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
US RTE 6 FROM LEXINGTON AVE TO FISK AVE

SUMMARY OF QUANTITIES

DATE 02/21/08
DRAWN BY J.R.P.
CHECKED BY M.R.F.