

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
351	2008-001VB	COOK	579	35
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 60E10				

**PROPOSED ROADWAY PAVEMENT**

LOCATION STATION - STATION US ROUTE 6	PCC PAVEMENT 260 MM (SQ. M.)	AGG. SUBGRADE (PCC) 300 MM (SQ. M.)	SUB-BASE GRAN. MATL. TY-B, 100 MM (SQ. M.)	HMA BASE 100 MM (SQ. M.)	HMA BINDER 100 MM (M. TON)	HMA SURFACE 50 MM (M. TON)
STA 2+682 - STA 2+700	334	334				
STA 2+700 - STA 3+101	8,807	8,807				
PARK AVE	6,676	6,675				
CENTER ST	2,055	2,055				
WEST AVE	2,185	2,185	1817	1817	226	180
<b>TOTALS</b>	<b>20,056</b>	<b>20,055</b>	<b>1817</b>	<b>1817</b>	<b>226</b>	<b>180</b>

**PROPOSED DRIVEWAY PAVEMENT**

LOCATION STATION US ROUTE 6	OFFSET	HMA BASE		HMA SURFACE	PCC PAVT		C&G	C&G
		150 MM (SQ. M.)	200 MM (SQ. M.)	50 MM (M. TON)	150MM (SQ. M.)	200MM (SQ. M.)	B-15.60 (M.)	B-15.30 (M.)
2+707.3	LT					34.2		
PARK AVE								
40+944.2	LT					20.4		
41+062.6	LT					20.2		
CENTER ST								
50+843.3	LT		44.2	5.4				
50+862.6	RT		80.4	9.9				
50+877.6	LT		44.3	5.4				
50+913.1	LT		50.2	6.2				
51+145.5	LT		64.1	78.8				42.1
51+251.3	LT		14.8	1.8				
51+259.5	RT		19.4	2.4				
<b>SUBTOTALS</b>		0.0	317.4	109.9	0.0	74.8	0.0	42.1
<b>TOTALS</b>		0.0	317.4	109.9	0.0	74.8	0.0	42.1

**DRIVEWAY PAVEMENT REMOVAL**

LOCATION STATION - STATION US ROUTE 6	AREA (SQ. M.)
2+694 (LT)	7
STA 2+700.0 - STA 2+825	
2+707.3(LT)	85
STA 2+825.0 - STA 2+950	
STA 2+950.0 - STA 3+100	
3+045 (LT)	25
SIDE STREETS	AREA
STATION	(SQ. M.)
PARK AVE	
40+944.2(LT)	22
41+062.6(LT)	23
CENTER ST	
50+802.6(RT)	80
50+843.3(LT)	40
50+877.6(LT)	40
50+913.1(LT)	45
50+943 (RT)	65
WEST AVE	
51+045 (RT)	48
<b>TOTAL</b>	<b>480</b>

**PAVEMENT REMOVAL**

LOCATION STATION - STATION US ROUTE 6	AREA (SQ. M.)
STA 2+682 - STA 2+700	282
STA 2+700 - STA 2+825	1,691
STA 2+825 - STA 2+950	1,482
STA 2+950 - STA 3+100	1,890
STA 3+100 - STA 3+250	10
PARK AVE	6,400
CENTER ST	1,780
WEST AVE	2,835
<b>TOTAL</b>	<b>16,370</b>

**PROPOSED COMBINATION CURB AND GUTTER (INCLUDES TEMP. CURB FOR PHASE I MOT)**

LOCATION US ROUTE 6 STATION - STATION	B-15.60 (M)	B-15.60 (TEMP.) (M)	B-15.30 (M)	AGG. SUBGRADE 300 mm (SQ. M)	LOCATION SIDE STREETS	B-15.60 (M)	B-15.60 (TEMP.) (M)	B-15.30 (M)	AGG. SUBGRADE 300 mm (SQ. M)
STA 2+595.0 - STA 2+700	71.7	6.0		53.7	PARK AVE(N)	397.0	132.0		297.8
STA 2+700.0 - STA 2+825	116.1	58.0		87.0	PARK AVE(S)	401.9	101.0		301.4
STA 2+825.0 - STA 2+950	250.0			187.5	WEST AVE	452.4	176.0	10.5	344.0
STA 2+950.0 - STA 3+100	202.0	96.0		151.5	CENTER ST	393.1			294.8
					FISSK AVE	29.6			22.2
COMMERCIAL DRIVEWAYS									
STA 51+145.4, LT.				42.1					
STA 51+170.9, LT.	13.39								
<b>SUBTOTAL</b>	<b>653.1</b>	<b>158.0</b>	<b>42.1</b>	<b>479.8</b>	<b>SUBTOTAL</b>	<b>1674.0</b>	<b>409.0</b>	<b>10.5</b>	<b>1260.2</b>
					<b>TOTAL</b>	<b>2327.1</b>	<b>567.0</b>		
					<b>GRAND TOTAL</b>	<b>2327</b>	<b>2894</b>	<b>53</b>	<b>1740</b>

**CURB REMOVAL AND COMBINATION CURB AND GUTTER REMOVAL (INCLUDES TEMP CURB FOR PHASE I MOT)**

LOCATION STATION - STATION US ROUTE 6	CURB REMOVAL (M.)	COMB. CURB AND GUTTER REMOVAL (M.)	COMB. CURB AND GUTTER REMOVAL (TEMP. CURB) (M.)
STA 2+682.0 - STA 2+700		36	6
STA 2+700.0 - STA 2+825	4	161	56
2+706.9(LT)			
STA 2+825.0 - STA 2+950	92	260	
STA 2+950.0 - STA 3+100		259	96
DIXIE HWY (S)			142
DIXIE HWY (N)			98
PARK AVE (S)		380	101
PARK AVE (N)		310	132
40+944.2(LT)	4		
CENTER ST		30	
WEST AVE		476	176
51+045 (RT)	12		
<b>TOTAL</b>	<b>112</b>	<b>1902</b>	<b>807</b>

**PROPOSED CONCRETE CURB TYPE B**

LOCATION	L (m)
2+707.3, LT. (ALLEY)	6.3
MAJOR CROSS STREETS	
40+944.2, LT. (ALLEY - PARK AVE.)	9.9
41+061.8, LT. (ALLEY)	5.0
50+843.3, LT. (DRIVEWAY - CENTER ST.)	14.1
50+862.3, RT. (DRIVEWAY)	15.3
50+878.4, LT. (DRIVEWAY)	14.6
50+912.8, LT. (DRIVEWAY)	14.3
51+251.3, RT. (DRIVEWAY - WEST AVE.)	6.5
<b>TOTAL:</b>	<b>86.0</b>

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION US RTE 6 FROM LEXINGTON AVE TO FISK AVE SCHEDULE OF QUANTITIES
NAME	DATE	