



CENTER STREET  
STA. 50+803.930 TO STA. 50+999.540

WEST AVENUE  
STA. 50+999.540 TO STA. 51+188.380

LEGEND, TRAFFIC MAINTENANCE			
③	200 mm TEMPORARY PAVEMENT	⑧	EXISTING CORRUGATED CONCRETE MEDIAN REMOVAL PARTIAL DEPTH
④	TEMPORARY CONCRETE CURB AND GUTTER, TYPE B-15.60 *	⑨	PORTLAND CEMENT CONCRETE PAVEMENT 260 mm (JOINTED)
⑤	TEMPORARY PAVEMENT MARKING TAPE, 100 mm, WHITE	⑩	AGGREGATE SUBGRADE 300 mm
⑤c	TEMPORARY PAVEMENT MARKING TAPE, 100mm, YELLOW W/YELLOW SKIP/DASH	⑪	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.60
⑤b	TEMPORARY PAVEMENT MARKING TAPE, 150mm, WHITE	⑫	TOPSOIL, 100 mm
⑤c	TEMPORARY PAVEMENT MARKING TAPE, 100mm, DOUBLE YELLOW	⑬	SODDING, SALT TOLERANT
⑥	TEMPORARY LIGHTED BARRICADE, DRUM, OR VERTICAL PANEL	⑭	SODDING
⑦	EXISTING PAVEMENT TO BE REMOVED	⑮	PORTLAND CEMENT CONCRETE SIDEWALK, 125 mm
		⑯	TEMP. BITUMINOUS AGGREGATE MIXTURE (BAM) INFILL (DEPTH VARIES)
		⑰	TEMPORARY SIDEWALK, MIN. 1.5 m WIDE (MAX. 2% SIDESLOPE)

\* PROVIDE FOR DEPRESSED CURB AT LOCATIONS OF EXISTING DRIVEWAYS

NOTE:  
ALL REFERENCE TO TYPE III TAPE SHALL BE TYPE III TEMPORARY TAPE FOR WET CONDITIONS.

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION US RTE 6 FROM LEXINGTON AVE TO FISK AVE MAINTENANCE OF TRAFFIC TYPICAL SECTIONS
NAME	DATE	
		MT-12B DATE 02/21/08 DRAWN BY MRF CHECKED BY JWK