3/13/2008 2:09:33 PM

q:\17049.069\Track & Rail Main Contract\FINAL PLANS\plan_temp_1.dgn

PERIMETER EROSION BARRIER

(CONSTRUCT AS SHOWN, LAYOUT MAY VARY AT THE DIRECTION OF THE ENGINEER.)
STA. 795+56, LT. TO STA. 799+28, LT. = 375 FT.
STA. 800+58, LT. TO STA. 803+00, LT. = 244 FT.
STA. 491+15, RT. TO STA. 499+88, RT. = 888 FT.
STA. 500+91, RT. TO STA. 504+00, RT. = 292 FT.
TOTAL = 1799 FT.

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
F.A.P. 351	2008-001VB	COOK	579	183
STA.	TO STA.			
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 60E10

LEGEND
- ℄ PROPOSED TRACK
- EXISTING TRACK
- PERIMETER EROSION BARRIER

* SEE INTERMODAL FACILITY GRADING, PAVING AND DRAINAGE SHEET FOR BILL OF MATERIAL FOR PAVEMENT REMOVAL AND HMA PAVEMENT ITEMS.

SEE INTERMODAL FACILITY GRADING, PAVING AND DRAINAGE SHEET FOR DETAILS OF PAVEMENT REMOVAL, CURB AND GUTTER REMOVAL AND TEMPORARY CONCRETE BARRIER

APPROXIMATE LOCATION OF UNDERGROUND GAS MAIN SERVING INTERMODAL TERMINAL BUILDING

CONSTRUCTION LIMITS

PERIMETER EROSION BARRIER (SEE STD. 280001 FOR DETAILS)

℄ TEMP. CN THOROUGHFARE TRACK

EXIST. CN THOROUGHFARE TRACK

U.S. ROUTE 6

MATCHLINE STA. 803+00.00 (℄ TEMP. CN THOROUGHFARE)

800+00

℄ PROP. U.S. RTE. 6

950+00

700+00

* 13.9 S.Y. PAVEMENT REMOVAL

* 14.1 S.Y. HMA PAVEMENT

TIMBER GRADE CROSSINGS TO BE ADJUSTED BY THE CN

PARKING

℄ TEMP. CN GATEWAY LEAD TRACK

EXIST. CN GATEWAY LEAD TRACK

CONSTRUCTION LIMITS

EXIST. CN TRACK 4
EXIST. CN TRACK 3
EXIST. CN TRACK 2
EXIST. CN TRACK 1

EXIST. STR. NO. 016-2754
℄ EXIST. TEMP. CN TRACK 4
℄ EXIST. TEMP. CN TRACK 3
℄ EXIST. TEMP. CN TRACK 2

℄ TEMP. CN TRACK 1
℄ TEMP. METRA TRACK 2
℄ TEMP. METRA TRACK 1

1695+00
1595+00
1495+00
1395+00
1295+00
1195+00
1095+00
600+00
500+00
400+00
300+00
200+00
100+00

MATCHLINE STA. 504+00.00 (℄ EXIST. CN TRACK 3)

TO CHICAGO

TO CHAMPAIGN

EXIST. METRA TRACK 2
EXIST. METRA TRACK 1

PARK AVENUE

PROP. CONST. ACCESS STEPS (SEE DETAIL SHEET)

U.S. ROUTE 6

CONSTRUCTION LIMITS

PERIMETER EROSION BARRIER (SEE STD. 280001 FOR DETAILS)

TO MILEPOST 20, 3487.3', ALONG ℄ EXISTING CN TRACK 3 STA. 465+12.70

REVISIONS NAME	DATE
REZ	10/19/07

ILLINOIS DEPARTMENT OF TRANSPORTATION
US RTE 6 FROM I-294 TO IL RTE 1
METRA & CN OVER 159TH STREET

TRACK CONSTRUCTION
GENERAL PLAN
TEMPORARY ALIGNMENTS

SHT. 9 OF 88 DRAWN BY REZ
DATE 2/21/2008 CHECKED BY RMS