
STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION


ſ	ROUTE NO. S		SECT	ION	COUNTY		TOTAL SHEETS		SHEET NO.
-	F.A.I 351	٥.	2008- 001VB		соок		579		427
7	FED. ROAD DIST. NO. 7			ILLINOIS	FED.	AID	PROJE	CT-	

54 SHEETS

CONTRACT NO. 60E10



INSIDE ELEVATION OF EAST PARAPET, SN 016-2820, LOOKING EAST REFLECTED INSIDE ELEVATION OF WEST PARAPET, SN 016-2821



INSIDE ELEVATION OF EAST CURB, SN 016-2820, LOOKING EAST INSIDE ELEVATION OF WEST CURB, SN 016-2821, LOOKING WEST

Non-staining gray one component non-sag elastomeric gun grade polyurethane sealant meeting the requirements of ASTM C-920. Type S, Grade NS, Class 25, Use T. 58" \phi Backer Rod-"2" Preformed Self-Expanding Cork Joint Filler according to Article 1051.07 of the Std. Spec. Cost included with Concrete -Superstructure. Const. Jts. at Piers Const. Jt. '8" Aluminum sheet ASTM (Optional) B 209 alloy 3003-H14. Cost included with Const. Jt. Concrete Superstructure (Mandatory)

Notes:

URS 500 Statte 500 Chicago, IL 60606 (312) 939-1000

- 1. Reinforcement bars designated (E) shall be epoxy coated.
- 2. Bars indicated thus 1 x 2-#5 etc. indicates 1 line of bars with 2 lengths per line.
- 3. Min. lap length for #4 bar is 1'-4", #5 bar is 1'-8" and #8 bar is 3'-8".
- 4. Work this Sheet with Sheets 13 through 16.
- 5. For bar bending details and Bill of Materials see Sheet 16.
- 6. If the Contractor elects to use cast-in-place anchor device for Parapet Railing post, then the Contractor must coordinate fabrication of the Parapet Railing with respect to as-built locations of the cast-in-place anchors. The Contractor shall correct any errors in fabrication of the Parapet Railing with respect to as-built locations of cast-in-place anchors at his own expense.

REVISIONS
NAME
DATE

BARAPET & CURB DETAILS

STRUCTURES FOR CN INTERMODAL
YARD VEHICLES OVER U.S. RTE. 6 (159TH STREET)
Sulte 500
Chloago, IL 60606

STATION 95+02.14

STRUCTURE NOS. 016-2820
STATION 95+02.14

SCALE: N.T.S.

DATE: 2/21/2008

PARAPET JOINT DETAILS

DESIGNED EV

CHECKED NPP

DRAWN EV