

SUMMARY OF QUANTITIES				URBAN 80% FED. 20% STATE	CONSTRUCTION TYPE CODE
CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY		ROADWAY 1000-2A
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	80		80
40600300	AGGREGATE (PRIME COAT)	TON	415		415
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	105		105
40600535	LEVELING BINDER (HAND METHOD), N70	TON	10		10
40600895	CONSTRUCTING TEST STRIP	EACH	2		2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	630		630
40600990	TEMPORARY RAMP	SQ YD	1,045		1,045
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	1,090		1,090
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	10,420		10,420
42001300	PROTECTIVE COAT	SQ YD	2,600		2,600
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	103,250		103,250
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	7,700		7,700
44002212	HOT-MIX ASPHALT SURFACE REMOVAL OVER PATCHES, 3"	SQ YD	6,280		6,280
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	50		50
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	3,240		3,240
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	1,080		1,080
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	1,090		1,090
NP 55039700	STORM SEWERS TO BE CLEANED	FOOT	7,500		7,500
60250200	CATCH BASINS TO BE ADJUSTED	EACH	1		1
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	85		85
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6		6
67100100	MOBILIZATION	L SUM	1		1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1		1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1		1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3,900		3,900
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	6030		6030
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	81,000		81,000
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	30,900		30,900
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	2,250		2,250
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	4,050		4,050
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	19,300		19,300

70102630 TRAFFIC CONTROL AND PROTECTION, STANDARD 701601 LSUM 1 1  
 \* DENOTES SPECIALTY ITEM  
 NP= Non-Participating  
 © 1980

SUMMARY OF QUANTITIES				URBAN 80% FED. 20% STATE	CONSTRUCTION TYPE CODE
CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY		ROADWAY 1000-2A
• 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	2010		2010
• 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	27,000		27,000
• 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	10,300		10,300
• 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	750		750
• 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1,350		1,350
• 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	990		990
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	890		890
• 88600600	DETECTOR LOOP REPLACEMENT	FOOT	7,600		7,600
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52		52
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD) IL-4.75, N50	TON	4,190		4,190
NP Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	190		190

© 20076600 TRAINERS  
 NP= Non-Participating

HOURL 1500 1500

FILE NAME = N:\PROJ\3329\3329\_38\Design\ProposedPlan\3229\_38-03-Quantities.dgn

**Ciorba Group, Inc.**  
 CONSULTING ENGINEERS  
 5507 North Cumberland Avenue, Suite 402  
 Chicago, Illinois 60656  
 Tel. 773.775.4009 Fax 773.775.4014

USER NAME = mbelog	DESIGNED - RD	REVISED -
PLOT SCALE = 1:2000' / IN.	DRAWN - RD	REVISED -
PLOT DATE = 4/8/2008	CHECKED - WBL	REVISED -
	DATE - 04/7/2008	REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

ILLINOIS ROUTE 58 BASSWOOD ROAD TO I-290 SUMMARY OF QUANTITIES			
SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
559	582R (I&J) RS-1	COOK	27	3
CONTRACT NO. 60E21			Rev.	
FED. ROAD DIST. NO. - [ILLINOIS] FED. AID PROJECT				