



REPLACE ALL DETECTOR LOOPS AS SHOWN
(WITHIN PROJECT LIMITS)

CODE NO.	QUANTITY	UNIT	ITEM
86600600	908	FOOT	DETECTOR LOOP REPLACEMENT

PLAN LEGEND	
	CONTROLLER FOUNDATION MODIFIED
	SERVICE INSTALLATION
	SIGNAL FACE OPTICALLY PROGRAMMED
	SIGNAL FACE
	EMERGENCY VEHICLES SYSTEM DETECTOR, OPTICAL TYPE
	SIGNAL FACE, PEDESTRIAN
	MAST ARM ASSEMBLY AND POLE
	HANDHOLE
	HEAVY DUTY HANDHOLE
	DOUBLE HANDHOLE
	G.S. CONDUIT IN TRENCH
	G.S. CONDUIT PUSHED
	RACEWAY FOR MAGNETIC DETECTOR, TYPE I
	RACEWAY FOR MAGNETIC DETECTOR, TYPE II
	VEHICLE DETECTOR, NON-COMPENSATED MAGNETIC TYPE
	PEDESTRIAN PUSH BUTTON DETECTOR
	CONDUIT SLICK
	CONCRETE JUNCTION BOX
	WOOD POLE
	SIGNAL FACE WITH BACKPLATE
	LOOP DETECTOR, 6' x 6' MULTIPLES (OR OTHERWISE NOTED)
	NEW POST (ON EXISTING FOUNDATION)
	EXISTING SIGNAL HEAD (TO BE REMOVED/RETAINED)
	EXISTING MASTARM (TO REMAIN)

EXISTING LEGEND	
	EXISTING CONDUIT
	HANDHOLE
	LOOP DETECTOR
	EXISTING MAGNETIC DETECTOR
	DISCONNECT PEDESTAL CABINET

FILE NAME: N:\PROJECTS\3521\3521_25\Design\3521_25\posse\plan\3521_25\3521_25_01.dwg

Ciorba Group, Inc.
CONSULTING ENGINEERS
5507 North Cumberland Avenue, Suite 402
Chicago, Illinois 60656
Tel. 773.775.4009 Fax 773.775.4014

USER NAME: mbelog	DESIGNED - RD	REVISED -
PLOT SCALE = 1:8000000 @ 1/4" = 100'	DRAWN - RD	REVISED -
PLOT DATE = 4/5/2008	CHECKED - WBL	REVISED -
	DATE - 04/7/2008	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**ILLINOIS ROUTE 58
BASSWOOD ROAD TO I-290
DETECTOR LOOP REPLACEMENT**

SCALE: N.T.S. SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
559	582 R (1 & 3) RS-1	COOK	27	15
CONTRACT NO. 60E21				
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT				