

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		URBAN 1000					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	1728	1728					
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SO YD	10283	10283					
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	7064	7064					
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	1632	1632					
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	1587	1587					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3					
67100100	MOBILIZATION	L SUM	1	1					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	16600	16600					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	104	104					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	104	104					
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	669	669					

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT							

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

PLOT DATE: 5/21/2008

5/21/2008
c:\projects\136008\design_aa.dgn