

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN ILL-53 I000-2A			
20201006	GRADING AND SHAPING SHOULDERS	UINT	197	197			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	57	57			
40600300	AGGREGATE (PRIME COAT)	TON	285	285			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	42.7	42.7			
40600895	CONSTRUCTING TEST STRIP	EACH	3	3			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	3382	3382			
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	871	871			
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	10179	10179			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	5953	5953			
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	49182	49182			
44002214	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3 1/2"	SO YD	4443	4443			
44201773	CLASS D PATCHES, TYPE I, 11 INCH	SO YD	4	4			
44201777	CLASS D PATCHES, TYPE II, 11 INCH	SO YD	24	24			
44201783	CLASS D PATCHES, TYPE IV, 11 INCH	SO YD	74	74			
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	788.2	788.2			
60255600	MANHOLES TO BE ADJUSTED (SPECIAL)	EACH	10	10			
64200105	SHOULDER RUMBLE STRIP	FOOT	14408	14408			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6			
67100100	MOBILIZATION	L SUM	1	1			
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	109,155	109,155			
70300530	PAVEMENT MARKING TAPE, TYPE III 5"	FOOT	18,895	18,895			
70300540	PAVEMENT MARKING TAPE, TYPE III 6"	FOOT	2060	2060			
70300550	PAVEMENT MARKING TAPE, TYPE III 8"	FOOT	16,620	16,620			
70300560	PAVEMENT MARKING TAPE, TYPE III 12"	FOOT	2028	2028			
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	58400	58400			

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN ILL-53 I000-2A			
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1030	1030			
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	8310	8310			
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1014	1014			
* 78003120	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 5"	FOOT	10460	10460			
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1200	1200			
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1200	1200			
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	496	496			
X0324685	TEST STRIP (STONE MATRIX ASPHALT)	EACH	2	2			
X4066580	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	11,736.3	11,736.3			
X4066685	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, STONE MATRIX ASPHALT, N80	TON	4102	4102			
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1276	1276			
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1			
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2	2			
X4420076	CLASS D PATCHES, TYPE I, 9 1/4 INCH	SO YD	244	244			
X4420077	CLASS D PATCHES, TYPE II, 9 1/4 INCH	SO YD	509	509			
X4420078	CLASS D PATCHES, TYPE III, 9 1/4 INCH	SO YD	555	555			
X4420079	CLASS D PATCHES, TYPE IV, 9 1/4 INCH	SO YD	1921	1921			
X4420092	CLASS D PATCHES, TYPE II, 9 1/2 INCH	SO YD	1777	1777			
X4420093	CLASS D PATCHES, TYPE III, 9 1/2 INCH	SO YD	1777	1777			
X4420099	CLASS D PATCHES, TYPE IV, 9 1/2 INCH	SO YD	889	889			
* X8850102	INDUCTION LOOP	FOOT	318	318			
20076400	TRAINEES	HOURL	4000	4000			
X0322300	ELECTRIC CABLE IN CONDUIT NO. 18 4/C, TWISTED, SHIELDED	FOOT	1395	1395			
B1900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	130	130			
X0322728	POLYETHYLENE DUCT 2"	FOOT	130	130			
B9502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	2284	2284			
X0326122	ELECTRIC CABLE ASSEMBLY IN CONDUIT, 600V (EPR-TYPE T) 4/C NO. 6 AND NO. 8 GROUND	FOOT	422	422			
X0323364	ELECTRIC CABLE IN CONDUIT, NO. 19 6/C	FOOT	422	422			
B1400200	HEAVY-DUTY HANDHOLE	EACH	2	2			
X0322729	MATERIAL TRANSFER DEVICE	TON	15,838	15,838			
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	10	10			

4/18/2008

* Specialty Items
© Y080

Rev. 5-30-08

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
ILLINOIS ROUTE 53 (EXTENSION)
LAKE-COOK ROAD TO U. S. 12 (RAND RD.)
SUMMARY OF QUANTITIES