

FAU RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3512	86Y-RS-3	COOK	35	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		80% FED. 20% STATE 1000	50% STATE 50% CITY PARK RIDGE Y025	100% CITY PARK RIDGE Y025		
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	600	600				
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	825	825				
20200100	EARTH EXCAVATION	CU YD	450	450				
20201006	GRADING AND SHAPING SHOULDERS	UNIT	90	90				
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SO YD	13	13				
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SO YD	13	13				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	44	37	7			
40600300	AGGREGATE (PRIME COAT)	TON	216	188	28			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	47	37	10			
40600895	CONSTRUCTING TEST STRIP	EACH	2	2				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	3200	3200				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	355	314		41		
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	161	161				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	9041	7915	1126			
42001300	PROTECTIVE COAT	SO YD	250	250				
44000124	BITUMINOUS REMOVAL OVER PATCHES 6"	SO YD	1030	910		120		
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	5592	5592				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	101217	87820	13397			
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	2230	1830		400		
44002224	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 6"	SO YD	1030	910		120		
44004610	SIDEWALK REMOVAL AND REPLACEMENT (SPECIAL)	SO FT	500	500				
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SO YD	100	100				
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	1050	950		100		
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	500	430		70		
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	1900	1900				
48101200	AGGREGATE SHOULDERS, TYPE B	TON	325	325				

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		80% FED. 20% STATE 1000	50% STATE 50% CITY PARK RIDGE Y025	100% CITY PARK RIDGE Y025		
55039700	STORM SEWERS TO BE CLEANED	FOOT	500	500				
60250200	CATCH BASINS TO BE ADJUSTED	EACH	20	20				
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	6	6				
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	116	116				
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	25	25				
63200310	GUARDRAIL REMOVAL	FOOT	200	200				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
67100100	MOBILIZATION	L SUM	1	1				
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1				
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	30	30				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	27804	15720		12084		
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	700	700				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	50830	50830				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	4000	4000				
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	250	250				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	190	190				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	735	735				
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	22225	22225				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	30093	26065		4028		
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	635	635				
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	53858	49830		4028		
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	4000	4000				

NP= Non-Participating
● SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
FAU 3512 BUSSE HIGHWAY