

NOTES:

- 1. USE BLACK LETTERING ON ORANGE BACKGROUND.
- 2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
- 3. ERECT SIGN (1) WITH INSTALLED PANEL (2) ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
- 4. REMOVE PANEL 2 SOON AFTER THE START OF CONSTRUCTION.
- 5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
- 7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS)
UNLESS OTHERWISE SHOWN.

	FILE NAME =	USER NAME = bauerdl	DESIGNED -	REVISED - R. MIRS 09-15-97
	K:\diststd22x34\te22.dgn		DRAWN -	REVISED - R. MIRS 12-11-97
		PLOT SCALE = 50.000 // IN.	CHECKED -	REVISED -T. RAMMACHER 02-02-99
1		PLOT DATE = 3/11/2008	DATE -	REVISED - C. JUCIUS 01-31-07

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

	ARTERIAL ROAD		F.AU. SECTION	COUNTY TOTAL SHEE SHEETS NO.
	INFORMATION SIGN		3512 86Y-RS-3	COOK 35 30
 SCALE: NONE SHEET	NO. 1 OF 1 SHEETS STA.	TO STA.	FED. ROAD DIST. NO. 1 ILLINOIS FED. A	CONTRACT NO.