

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
324	24N-1	McHENRY	82	4
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	
CONTRACT# 62296				

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES 90% FED. / 10% STATE	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		ROADWAY 1000-2A				
M542H025	PIPE CULVERTS, CLASS A, TYPE 1 375MM	METER	28	28				
M542H030	PIPE CULVERTS, CLASS A, TYPE 1 450MM	METER	59	59				
M542T020	PIPE CULVERTS, CLASS A, TYPE 1 375MM (TEMPORARY)	METER	40	40				
M5505530	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 300MM	METER	76	76				
M5505540	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 375MM	METER	35	35				
M5505550	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 450MM	METER	4	4				
M5505930	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 300MM	METER	236	236				
M5505940	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 375MM	METER	166	166				
M5505950	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 450MM	METER	26	26				
M6010605	PIPE UNDERDRAINS 100MM	METER	285	285				
M6020140	CATCH BASINS, TYPE A, 1.2M DIAMETER, TYPE 8 GRATE	EACH	2	2				
M6020180	CATCH BASINS, TYPE A, 1.2M DIAMETER, TYPE 23 FRAME AND GRATE	EACH	10	10				
M6021410	MANHOLES, TYPE A, 1.2M DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	12	12				
M6060070	CONCRETE CURB, TYPE B	METER	5	5				
M6061930	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-10.30	METER	670	670				
*M6300100	STEEL PLATE BEAM GUARD RAIL, TYPE A	METER	135	135				
M6320020	STEEL PLATE BEAM GUARD RAIL REMOVAL	METER	135	135				
M6650100	WOVEN WIRE FENCE, 1.2 METER	METER	95	95				
M6650420	WOVEN WIRE FENCE REMOVAL	METER	95	95				
M7030100	SHORT-TERM PAVEMENT MARKING	METER	440	440				
M7030210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ M	21	21				
M7030220	TEMPORARY PAVEMENT MARKING - LINE 100MM	METER	6000	6000				
M7030240	TEMPORARY PAVEMENT MARKING - LINE 150MM	METER	265	265				
M7030260	TEMPORARY PAVEMENT MARKING - LINE 300MM	METER	130	130				
M7030280	TEMPORARY PAVEMENT MARKING - LINE 600MM	METER	44	44				

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES 90% FED. / 10% STATE	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		ROADWAY 1000-2A				
M7030520	PAVEMENT MARKING TAPE, TYPE III 100MM	METER	1700	1700				
M7031000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ M	44	44				
M7040100	TEMPORARY CONCRETE BARRIER	METER	145	145				
*M7800100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ M	21	21				
*M7800105	THERMOPLASTIC PAVEMENT MARKING - LINE 100MM	METER	6000	6000				
*M7800115	THERMOPLASTIC PAVEMENT MARKING - LINE 150MM	METER	265	265				
*M7800125	THERMOPLASTIC PAVEMENT MARKING - LINE 300MM	METER	130	130				
*M7800140	THERMOPLASTIC PAVEMENT MARKING - LINE 600MM	METER	44	44				
M7830100	PAVEMENT MARKING REMOVAL	SQ M	70	70				
MX030199	TEMPORARY PAVEMENT	SQ M	3445	3445				
MX030217	PIPE CULVERT REMOVAL 375MM	METER	68	68				
MX030218	PIPE CULVERT REMOVAL 450MM	METER	57	57				
M5424820	PIPE CULVERTS, PIPE 2, REINFORCED CONCRETE ELLIPTICAL EQUIVALENT ROUNDS - SIZE 600 MM	METER	7.2	7.2				
MX032178	TEMPORARY INFORMATION SIGNING	SQ M	9.2	9.2				
M5421055	PIPE CULVERTS, CLASS A, TYPE 2 400 MM	METER	25	25				
MX032842	BOX CULVERT REMOVAL	METER	10	10				
MX033447	PIPE CULVERT REMOVAL, 600MM	METER	0.6	0.6				
MX207010	POROUS GRANULAR EMBANKMENT, SUBGRADE 300MM	SQ M	1010	1010				
MZ001050	AGGREGATE SUBGRADE 300MM	SQ M	7142	7142				
X0504200	CONCRETE HEADWALL	EACH	2	2				
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	9	9				
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	4	4				
XX005569	MAILBOX REMOVAL AND REINSTALLATION	EACH	6	6				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1				
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2				
Z0077800	WOOD POST	EACH	2	2				
*X0325936	SOLAR-POWERED FLASHER/POST MOUNTED (YELLOW LED DISPLAY)	EACH	2	2				
M3560465	HOT-MIX ASPHALT BASE COURSE WIDENING, 165 MM	SQ M	672	672				
@Z0076600	TRAINERS	HOURL	500	500				

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION	
NAME	DATE	SUMMARY OF QUANTITIES	

© 1980
* SPECIALTY ITEMS

2/13/2008 10:58:00 AM