

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
348	1214 & 3127-1RS-1	COOK	86	5
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			80% FED. 20% STATE URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		MA I000 IL-43	MA I000 111ST ST.	BHF X028-2A CULVERT REHAB	CODE NO	ITEM	UNIT		I0002A IL-43	I000 111ST ST.	CULVERT REHAB
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SO FT	704			704							
X0325389	SILT CURTAIN REMOVAL	SO YD	25			25							
X0329891	SILT CURTAIN	SO YD	25			25							
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	10179	9918	261								
X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SO YD	45930	44446	1484								
50104650	SLOPEWALL REMOVAL	SO YD	238.6			238.6							
Z0005305	BOX CULVERTS TO BE CLEANED	FOOT	421			421							
Z0013798	CONSTRUCTION LAYOUT	L SUM	1			1							
Z0017202	DOWEL BARS 1 1/2"	EACH	200	200									
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	50	50									
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	2									
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1									
Z0064800	SELECTIVE CLEARING	UNIT	39			39							
Z0075300	TIE BARS	EACH	74	74									
Z0076600	TRAINEES	HOUR	2500	2500									

NP - NON-PARTICIPATING
© Y080

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
IL-43 (HARLEM AVE.)
US 6 TO IL-7

Rev. REV. 01-10-08