

SUMMARY OF QUANTITIES				URBAN TOTAL QUANTITY 80% FED. 20% STATE	CONSTRUCTION TYPE CODE ROADWAY 1000-2A
CODE NO.	DESCRIPTION	UNIT			
20201006	GRADING AND SHAPING SHOULDERS	UNIT	100	100	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	100	100	
40600300	AGGREGATE (PRIME COAT)	TON	500	500	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	120	120	
40600535	LEVELING BINDER (HAND METHOD), N70	TON	10	10	
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	680	680	
40600990	TEMPORARY RAMP	SQ YD	1,150	1,150	
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	2,630	2,630	
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	11,900	11,900	
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	117,700	117,700	
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	600	600	
44002220	HOT-MIX ASPHALT SURFACE REMOVAL OVER PATCHES, 5"	SQ YD	9,110	9,110	
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	2,670	2,670	
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	2,160	2,160	
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	3,090	3,090	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	410	410	
NP 55039700	STORM SEWERS TO BE CLEANED	FOOT	4,500	4,500	
60250200	CATCH BASIN TO BE ADJUSTED	EACH	5	5	
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	140	140	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	8,080	8,080	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	2,190	2,190	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	201,300	201,300	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	11,700	11,700	
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	1,890	1,890	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	2,550	2,550	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	3,150	3,150	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	28,500	28,500	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	730	730	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	67,100	67,100	

SUMMARY OF QUANTITIES				URBAN TOTAL QUANTITY 80% FED. 20% STATE	CONSTRUCTION TYPE CODE ROADWAY 1000-2A
CODE NO.	DESCRIPTION	UNIT			
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3,900	3,900	
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	630	630	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	850	850	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1,050	1,050	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,800	1,800	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1,710	1,710	
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	2,900	2,900	
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	103	103	
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	4,780	4,780	
NP Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	140	140	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	

* 80074000 TRAINERS
 * DENOTES SPECIALTY ITEM
 NP= Non-Participating
 @ Y080

Hour 2000 2000

FILE NAME = N:\PROJ\3329\3329_36\Design\Proposals\Plan_3329_36-03-Quantities.dgn

CG
Ciorba Group, Inc.
 CONSULTING ENGINEERS
 5507 North Cumberland Avenue, Suite 402
 Chicago, Illinois 60656
 Tel. 773.775.4009 Fax 773.775.4014

USER NAME = mbelog	DESIGNED AL	REVISED -
PLOT SCALE = 1.0000' / IN.	DRAWN AL	REVISED -
PLOT DATE = 4/7/2008	CHECKED MJL	REVISED -
	DATE 4/7/2008	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

DES PLAINES RIVER ROAD
FOSTER AVENUE TO 1ST AVENUE (IL 171)
SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2710	3222 RS-1	COOK	31	3
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT			CONTRACT NO. 62414	

Rev.