

ACNHF      ACBHF      ←      ACNHF

ITEM NO.	ITEMS	UNIT	URBAN QUANTITY	ROADWAY		CULVERTS	LANDSCAPING	RETAINING WALLS	TRAFFIC SIGNALS						EMERGENCY VEHICLE PREEMPTION		RIGHT TURN LN (STA. 3167+50 TO STA. 3177+30)	SIDEWALK	
				80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	IL RT 59 @ BLACK ROAD	IL RT 59 @ VERTIN BLVD	IL RT 59 @ STA. 3122+00 LEFT	IL RT 59 @ THEODORE ST	IL RT 59 @ VERMETTE CIRCLE	IL RT 59 @ CATON FARM ROAD	INTERCONNECT	100% SHOREWOOD	100% JOLIET	100% JOLIET	50% STATE 50% SHOREWOOD	50% STATE 50% JOLIET
				J000-2A	X028-2A	Y003	Y007	Y031-1F	Y031-3D	J000-1A	SFTY-1B								
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	1,189	1,189															
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	88,062	15,873													20,905	51,284	
42400800	DETECTABLE WARNINGS	SQ FT	990	720													90	180	
44000100	PAVEMENT REMOVAL	SQ YD	96,052	96,052															
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	8,240	8,240															
44000300	CURB REMOVAL	FOOT	280	280															
44000500	COMBINATION CURB AND CUTTER REMOVAL	FOOT	15,684	15,684															
44000600	SIDEWALK REMOVAL	SQ FT	20,099	20,099															
44002400	CURB REMOVAL (SPECIAL)	FOOT	82	82															
44003100	MEDIAN REMOVAL	SQ FT	2,333	2,333															
44003800	MEDIAN SURFACE REMOVAL	SQ FT	9,067	9,067															
44004250	PAVED SHOULDER REMOVAL	SQ YD	4,613	4,613															
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SQ YD	100	100															
44200148	PAVEMENT PATCHING, TYPE III, 12 INCH	SQ YD	244	244															
44200150	PAVEMENT PATCHING, TYPE IV, 12 INCH	SQ YD	1,240	1,240															
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1,088	1,088															
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	1,061	1,061															
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1														
50104400	CONCRETE HEADWALL REMOVAL	EACH	2	2															
50200100	STRUCTURE EXCAVATION	CU YD	4,059				4,059												
50300225	CONCRETE STRUCTURES	CU YD	1,043				1,043												
50800105	REINFORCEMENT BARS	POUND	179,880		179,880														
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	147,240		1,420		145,820												
50800515	BAR SPLICERS	EACH	253		253														
50900805	PEDESTRIAN RAILING	FOOT	199		13		186												
51500100	NAME PLATES	EACH	1		1														
54001000	BOX CULVERT END SECTIONS	EACH	1	1															
54003000	CONCRETE BOX CULVERTS	CU YD	934.4		934.4														
54010404	PRECAST CONCRETE BOX CULVERT 4' X 4'	FOOT	87.0	87															
54200430	PIPE CULVERTS, TYPE 1 RCCP 15"	FOOT	241	241															
54201270	PIPE CULVERTS, TYPE 2 RCCP 15"	FOOT	51	51															
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	6	6															
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	13	13															
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1	1															
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1															
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	1	1															
54213870	STEEL END SECTIONS 15"	EACH	4	4															
54213879	STEEL END SECTIONS 24"	EACH	1	1															
54213903	STEEL END SECTIONS 48"	EACH	1	1															
54214515	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 30"	EACH	1	1															
5421D012	PIPE CULVERTS, CLASS D, TYPE 1 12" (TEMPORARY)	FOOT	67	67															
5421D015	PIPE CULVERTS, CLASS D, TYPE 1 15" (TEMPORARY)	FOOT	124	124															
5421D024	PIPE CULVERTS, CLASS D, TYPE 1 24" (TEMPORARY)	FOOT	75	75															
5421D042	PIPE CULVERTS, CLASS D, TYPE 1 42" (TEMPORARY)	FOOT	40	40															

● SPECIALITY ITEM  
 \*\* 100% SHOREWOOD QUANTITIES NOT IDENTIFIED IN FUNDING BREAKDOWNS NOTED ABOVE

REVISIONS	
NAME	DATE
REVISED IL59 ALIGN.	12/22/06

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**  
 ILLINOIS ROUTE 59

DATE 3/18/08  
 DRAWN BY FA  
 CHECKED BY RCB

SCALE: NONE

PLAN: 114R-1  
 PROFILE: 114R-1  
 DATE: 12/22/06  
 DRAWN BY: FA  
 CHECKED BY: RCB  
 PROJECT: ILLINOIS ROUTE 59  
 COUNTY: WILL  
 SECTION: 114R-1