

FAP RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338	(113 & 114) R-5	WILL	525	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FAP 338 (IL RTE. 59)	

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITY	TRAFFIC SIGNALS									
				ROADWAY & DRAINAGE 80% FED 20% STATE	TRAFFIC SIGNALS IL 59 @ FRASER 80% FED 10% STATE 10% VILLAGE	TRAFFIC SIGNALS IL 59 @ RENWICK 80% FED 10% STATE 10% COUNTY	TRAFFIC SIGNALS IL 59 @ FORT BEGGS 80% FED 13.3% STATE 6.7% VILLAGE	TRAFFIC SIGNALS INTERCONNECT 80% FED 20% STATE	TRAFFIC SIGNALS TEMPORARY INTERCONNECT 80% FED 20% STATE	TRAFFIC SIGNALS EVP EQUIPMENT 100% VILLAGE	WATER MAIN/ SANITARY SEWER 100% VILLAGE	SIDEWALK 50% STATE 50% VILLAGE	
				J000-2A	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-3D	Y060	SPN-1B
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	937	937									
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	932	932									
20101100	TREE TRUNK PROTECTION	EACH	102	102									
20101200	TREE ROOT PRUNING	EACH	102	102									
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	81	81									
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	21	21									
20200100	EARTH EXCAVATION	CU YD	20,455	20,455									
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	8,041	8,001								40	
20400800	FURNISHED EXCAVATION	CU YD	71,779	71,779									
* 20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	6,651	6,651									
20800150	TRENCH BACKFILL	CU YD	11,160	11,160									
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	27,161	27,161									
21101630	TOPSOIL FURNISH AND PLACE, 8"	SQ YD	53,471	53,471									
21101645	TOPSOIL FURNISH AND PLACE, 12"	SQ YD	7,359	7,359									
21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	200	200									
* 25000210	SEEDING, CLASS 2A	ACRE	13.70	13.70									
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	2,349	2,349									
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	2,349	2,349									
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	2,349	2,349									
25100630	EROSION CONTROL BLANKET	SQ YD	218,825	218,825									
25200110	SODDING, SALT TOLERANT	SQ YD	24,217	24,217									
25200200	SUPPLEMENTAL WATERING	UNIT	243	243									
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	3,220	3,220									
* 28000300	TEMPORARY DITCH CHECKS	EACH	55	55									
28000510	INLET FILTERS	EACH	340	340									

- * SPECIAL PROVISION
- SPECIALITY ITEM
- ∞ CONSTRUCTION CODE Y080
- VILLAGE = VILLAGE OF PLAINFIELD
- COUNTY = WILL COUNTY

ILLINOIS DEPARTMENT OF TRANSPORTATION
DISTRICT NO. 1 SCHAUMBURG

SUMMARY OF QUANTITIES

SCALE NONE
DATE MARCH 18, 2008

DRAWN BY JMH
CHECKED BY JCM