

FAP NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338	(113 & 114) R-5	WILL	525	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS		
		FAP 338 (IL RTE. 59)		

SUMMARY OF QUANTITIES													
CODE NO	ITEM	UNIT	TOTAL QUANTITY	ROADWAY & DRAINAGE		TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS INTERCONNECT	TRAFFIC SIGNALS	TRAFFIC SIGNALS	WATER MAIN/SANITARY SEWER	SIDEWALK
				80% FED	20% STATE	IL 59 @ FEENEY/FRASER	IL 59 @ RENWICK	IL 59 @ FORT BEGGS		TEMPORARY INTERCONNECT	EVP EQUIPMENT		
				J000-2A	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-3D	Y060	SPY-1B
28100107	STONE RIPRAP, CLASS A4	SQ YD	90	90									
28200200	FILTER FABRIC	SQ YD	90	90									
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	44,931	30,130									8793**
35100700	AGGREGATE BASE COURSE, TYPE A 8"	SQ YD	262	262									
35300400	PORTLAND CEMENT CONCRETE BASE COURSE 9"	SQ YD	624	624									
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	640	640									
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	2,444	2,444									
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,020	1,020									
40600300	AGGREGATE (PRIME COAT)	TON	20	20									
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	552	552									
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	270	270									
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	182	182									
42000416	PORTLAND CEMENT CONCRETE PAVEMENT 9 3/4" (JOINTED)	SQ YD	89,112	89,112									
42001300	PROTECTIVE COAT	SQ YD	25,796	25,796									
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	177	177									
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	1,245	1,245									
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	66,021	27,428									38,593
42400410	PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH	SQ FT	6,270	3,388									2,882
42400800	DETECTABLE WARNINGS	SQ FT	322	226									98
44000100	PAVEMENT REMOVAL	SQ YD	62,592	62,592									
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	3,410	3,410									
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	6,567	6,567									
44000300	CURB REMOVAL	FOOT	2,502	2,502									
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	7,872	7,872									
44000600	SIDEWALK REMOVAL	SQ FT	22,619	22,619									

- * SPECIAL PROVISION
 - SPECIALITY ITEM
 - ∞ CONSTRUCTION CODE Y080
- VILLAGE = VILLAGE OF PLAINFIELD
COUNTY = WILL COUNTY

**100% VILLAGE OF PLAINFIELD

ILLINOIS DEPARTMENT OF TRANSPORTATION
DISTRICT NO. 1 SCHAUMBURG

SUMMARY OF QUANTITIES

SCALE NONE
DATE MARCH 18, 2008

DRAWN BY JMH
CHECKED BY JCM

Rev. 5-30-08