

FAP NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338	(113 & 114) R-5	WILL	525	10
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FAP 338 (IL RTE. 59)		

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITY	ROADWAY & DRAINAGE		TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS INTERCONNECT	TRAFFIC SIGNALS TEMPORARY	TRAFFIC SIGNALS	WATER MAIN/ SANITARY SEWER	SIDEWALK
				80% FED 20% STATE	80% FED 10% STATE 10% VILLAGE	IL 59 @ FRASER 80% FED 10% STATE 10% VILLAGE	IL 59 @ RENWICK 80% FED 10% STATE 10% COUNTY	IL 59 @ FORT BEGGS 80% FED 13.3% STATE 6.7% VILLAGE		80% FED 20% STATE	80% FED 20% STATE		
				J000-2A	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-3D	Y060	5FT-1B
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	3,248	3,248									
60606000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	37,882	37,882									
* 60619124	CONCRETE MEDIAN, TYPE SB-6 (SPECIAL)	SQ FT	14,276	14,276									
60619200	CONCRETE MEDIAN, TYPE SB-6.06	SQ FT	41	41									
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	1,704	1,704									
60620000	CONCRETE MEDIAN, TYPE SB-6.24	SQ FT	10,385	10,385									
* 60900515	CONCRETE THRUST BLOCKS	EACH	8									8	
O 63301210	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	310	310									
O 63302000	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1									
67000600	ENGINEER'S FIELD LABORATORY	CAL MO	22	22									
* 67100100	MOBILIZATION	L SUM	1	1									
* 70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1									
* 70102550	TRAFFIC CONTROL AND PROTECTION FOR DETOUR <i>TEMPORARY</i>	EACH	1	1									
* 70103816	TRAFFIC CONTROL SURVEILLANCE	CAL MO	21	21									
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	84	84									
△ 70300100	<del>SHORT TERM PAVEMENT MARKING</del>	<del>FOOT</del>	<del>12,270</del>	<del>12,270</del>									
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	364	364									
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	63,764	63,764									
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1,043	1,043									
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	264	264									
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	268	268									
70300510	PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	1,386	1,386									
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	119,096	119,096									
70300540	PAVEMENT MARKING TAPE, TYPE III 6"	FOOT	5,026	5,026									
70300550	PAVEMENT MARKING TAPE, TYPE III 8"	FOOT	510	510									

- \* SPECIAL PROVISION
  - O SPECIALITY ITEM
  - ∞ CONSTRUCTION CODE Y080
- VILLAGE = VILLAGE OF PLAINFIELD  
COUNTY = WILL COUNTY

ILLINOIS DEPARTMENT OF TRANSPORTATION  
DISTRICT NO. 1 SCHAUMBURG

SUMMARY OF QUANTITIES

SCALE NONE  
DATE MARCH 18, 2008  
DRAWN BY JMH  
CHECKED BY JCM

Rev. 5-30-08

Rev. 04-18-08 JCM