

FAP NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338	(113 & 114) R-5	WILL.	525	51
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FAP 338 (IL RTE. 59)	

FROM STRUCTURE	TO STRUCTURE	SIZE	55019500	55019600	55019900	55020100	55020300	55021600	55021700	55021800	55021900	55022000	55022200	55022400	55022500	55034700	54010803	XX006642	20800150		
		(IN)	(FT)	(FT)	(FT)	(FT)	(FT)	(FT)	(FT)	(FT)	(FT)	(FT)	(FT)	(FT)	(FT)	(FT)	(FT)	(FT)	(FT)		
384	EX MH	12						5													
389	EX MH	15																			
313	TEE	12						17													
320	TEE	12						17													
322	TEE	12						22													
332	329	12						20													
346	TEE	12						17													
TOTALS			1044	13	727	766	327	7380	1467	1125	621	1931	816	1827	190	325	506	543	190	124	11015

TRENCH BACKFILL SUBTOTAL FOR STORM SEWER

PIPE CULVERT SCHEDULE

From Structure #	To Structure #	Size	54200430	54200433	54200439	54200445	20800150
			PIPE CULVERTS, TYPE 1, RCCP 15"	PIPE CULVERTS, TYPE 1, RCCP 18"	PIPE CULVERTS, TYPE 1, RCCP 24"	PIPE CULVERTS, TYPE 1, RCCP 30"	TRENCH BACKFILL (CY)
18	16	24	0	0	10	0	6.6
31	32	24	0	0	38	0	6.1
66	67	24	0	0	60	0	6.5
102	101	15	34	0	0	0	10.8
116	115	18	0	25	0	0	7.4
175	175A	30	0	0	0	8	0.0
181	181B	30	0	0	0	8	0.0
245	243	30	0	0	0	101	105.4
TOTALS			34	25	108	117	145

TRENCH BACKFILL SUBTOTAL FOR PIPE CULVERT

20800150	
TRENCH BACKFILL (CY)	
STORM SEWER PIPE CULVERTS	11015
	145
TOTAL	11160

STORM SEWER JACKED IN PLACE, 12" (SPECIAL)			
FROM STRUCTURE	TO STRUCTURE	PIPE SIZE	LENGTH
		(IN)	(FT)
309	308	12	66
339	338	12	63
TOTAL			129

REVISIONS	
NAME	DATE
ADDENDUM A	05-13-08

ILLINOIS DEPARTMENT OF TRANSPORTATION
DISTRICT NO. 1 SCHAUMBURG

STORM SEWER
SCHEDULE OF QUANTITIES

SCALE AS SHOWN
DATE MARCH 18, 2008

DRAWN BY JMH
CHECKED BY JCM