

SECTION	COUNTY	TOTAL SHEETS	SHEET NO
338 (113 & 114) R-5	WILL	525	5
STA.	TO STA.		
FED. ROAD DIST. NO.	BLINDS	FAP 338 (IL RTE. 59)	

SUMMARY OF QUANTITIES												
CODE NO	ITEM	UNIT	TOTAL QUANTITY	ROADWAY & DRAINAGE 80% FED 20% STATE	TRAFFIC SIGNALS IL 59 @ FRASER 80% FED 10% STATE 10% VILLAGE	TRAFFIC SIGNALS IL 59 @ RENWICK 80% FED 10% STATE 10% COUNTY	TRAFFIC SIGNALS IL 59 @ FORT BEGGS 80% FED 13.3% STATE 6.7% VILLAGE	TRAFFIC SIGNALS INTERCONNECT 80% FED 20% STATE	TRAFFIC SIGNALS TEMPORARY INTERCONNECT 80% FED 20% STATE	TRAFFIC SIGNALS EVP EQUIPMENT 100% VILLAGE	WATER MAIN/ SANITARY SEWER 100% VILLAGE	SIDEWALK 50% STATE 50% VILLAGE
				J000-2A	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-3D	Y060	SEY-1B
28100107	STONE RIPRAP, CLASS A4	SQ YD	90	90								
28200200	FILTER FABRIC	SQ YD	90	90								
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	33,984	33,984								
35100700	AGGREGATE BASE COURSE, TYPE A 8"	SQ YD	262	262								
35300400	PORTLAND CEMENT CONCRETE BASE COURSE 9"	SQ YD	624	624								
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	640	640								
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	2,444	2,444								
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,020	1,020								
40600300	AGGREGATE (PRIME COAT)	TON	20	20								
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	552	552								
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	270	270								
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	182	182								
42000416	PORTLAND CEMENT CONCRETE PAVEMENT 9 3/4" (JOINTED)	SQ YD	89,112	89,112								
42001300	PROTECTIVE COAT	SQ YD	25,796	25,796								
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	177	177								
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	1,245	1,245								
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	66,021	27,428								38,593
42400410	PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH	SQ FT	6,145	3,388								2,757
42400800	DETECTABLE WARNINGS	SQ FT	322	226								96
44000100	PAVEMENT REMOVAL	SQ YD	62,592	62,592								
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	3,410	3,410								
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	6,567	6,567								
44000300	CURB REMOVAL	FOOT	2,502	2,502								
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	7,872	7,872								
44000600	SIDEWALK REMOVAL	SQ FT	22,619	22,619								

- * SPECIAL PROVISION
- SPECIALITY ITEM
- ∞ CONSTRUCTION CODE Y080
- VILLAGE = VILLAGE OF PLAINFIELD
- COUNTY = WILL COUNTY

ILLINOIS DEPARTMENT OF TRANSPORTATION
DISTRICT NO. 1 SCHAUMBURG

SUMMARY OF QUANTITIES

SCALE NONE
DATE MARCH 18, 2009
DRAWN BY JMH
CHECKED BY JCM