

FAP R/C	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338	(113 & 114) R-5	WILL	525	6
STA.	TO STA.			
FED. ROAD DIST. NO.	MILEAGE	FAP 338 (IL RTE. 59)		

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITY	TRAFFIC SIGNALS									
				ROADWAY & DRAINAGE 80% FED 20% STATE	TRAFFIC SIGNALS IL 59 @ FEENEY/ FRASER 80% FED 10% STATE 10% VILLAGE	TRAFFIC SIGNALS IL 59 @ RENWICK 80% FED 10% STATE 10% COUNTY	TRAFFIC SIGNALS IL 59 @ FORT BEGGS 80% FED 13.3% STATE 6.7% VILLAGE	TRAFFIC SIGNALS INTERCONNECT 80% FED 20% STATE	TRAFFIC SIGNALS TEMPORARY INTERCONNECT 80% FED 20% STATE	TRAFFIC SIGNALS EVP EQUIPMENT 100% VILLAGE	WATER MAIN/ SANITARY SEWER 100% VILLAGE	SIDEWALK 50% STATE 50% VILLAGE	
				J000-2A	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-3D	Y060	SFTY-1B
44003100	MEDIAN REMOVAL	SQ FT	4,096	4,096									
44200108	PAVEMENT PATCHING, TYPE II, 9 INCH	SQ YD	57	57									
44200112	PAVEMENT PATCHING, TYPE III, 9 INCH	SQ YD	114	114									
44200114	PAVEMENT PATCHING, TYPE IV, 9 INCH	SQ YD	171	171									
* 44201717	CLASS D PATCHES, TYPE II, 6 INCH	SQ YD	52	52									
* 44201721	CLASS D PATCHES, TYPE III, 6 INCH	SQ YD	42	42									
* 44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	15	15									
* 44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	58	58									
* 44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	639	639									
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	4,023	4,023									
* 48101498	AGGREGATE SHOULDERS, TYPE B 4"	SQ YD	3,814	3,814									
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	252	252									
* 50105220	PIPE CULVERT REMOVAL	FOOT	1,291	1,291									
50300290	CONCRETE ENCASEMENT	CU YD	6.6	6.6									
54010503	PRECAST CONCRETE BOX CULVERT 5' X 3'	FOOT	106	106									
54010803	PRECAST CONCRETE BOX CULVERT 8' X 3'	FOOT	506	506									
54200430	PIPE CULVERTS, TYPE 1 RCCP 15"	FOOT	34	34									
54200433	PIPE CULVERTS, TYPE 1 RCCP 18"	FOOT	25	25									
54200439	PIPE CULVERTS, TYPE 1 RCCP 24"	FOOT	108	108									
54200445	PIPE CULVERTS, TYPE 1 RCCP 30"	FOOT	117	117									
5421C012	PIPE CULVERTS, CLASS C, TYPE 1 12" (TEMPORARY)	FOOT	636	636									
5421C024	PIPE CULVERTS, CLASS C, TYPE 1 24" (TEMPORARY)	FOOT	16	16									
5421C030	PIPE CULVERTS, CLASS C, TYPE 1 30" (TEMPORARY)	FOOT	25	25									
54213680	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	2	2									

- * SPECIAL PROVISION
 - SPECIALITY ITEM
 - ∞ CONSTRUCTION CODE Y080
- VILLAGE = VILLAGE OF PLAINFIELD
COUNTY = WILL COUNTY

ILLINOIS DEPARTMENT OF TRANSPORTATION
DISTRICT NO. 1 SCHAUMBURG

SUMMARY OF QUANTITIES

Rev. 04-18-08 JCM

SCALE NONE
DATE MARCH 18, 2008

DRAWN BY JMH
CHECKED BY JCM